

SURVEY & REMONUMENTATION

APR 05 1996

COMMISSION

**OTTAWA COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE**

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Ottawa
(County)

Located In: _____ Corner Code # _____

1. Public Land Survey T5N R15W A-10
T _____ R _____
T _____ R _____
T _____ R _____
(W 1/4 cor Sec.
30, Holland Twp)

2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____
Common cor

3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____
w/ M-10,
Park Township

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

RECORDED
95 NOV 15 PM 2:10
Richard D. Holloman
REGISTER OF DEEDS
OTTAWA COUNTY, MI
Register of Deeds Stamp & File Number

I, Steven Lampen _____, in a field survey on October 12, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
A-10
GLO - 1831 LCRC L 6-P' 265
Surveyor - Lucius Lyon NW corner of porch foundation 302° 50' 108.86'
12" W. Oak N 20° W 11' SW corner of brick house 54° 53' 106.71'
12" W. Oak S 40° W 20' NE corner of house foundation 119° 50' 111.56'
NW corner of brick house 250° 10' 135.16'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
A-10
Found CIM and is accepted as a careful and faithful perpetuation of the position of the original corner.

AZ
NW corner of porch foundation 302° 50' 108.86'
12" W. Oak N 20° W 11' SW corner of brick house 54° 53' 106.71'
12" W. Oak S 40° W 20' NE corner of house foundation 119° 50' 111.56'
NW corner of brick house 250° 10' 135.16'

P.A. 345 OTTAWA COUNTY
PEER APPROVED 10/23/95
Richard D. Holloman

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
A-10
CIM AZ
NW corner of porch foundation 302° 59' 108.86'
SW corner of brick house 54° 53' 106.71'
NE corner of house foundation 119° 50' 111.56'
NW corner of brick house 250° 10' 135.16'
This monument fits the six adjacent plats: Oosting's Subd., Hyma's Supervisor's Resubd., Oaklawn Park, Ingleside Plat, Heneveld's Supervisor's Plats 15 and 16.
Historically there is no jog at this corner.

Signed by Steven Lampen Date October 23, 1995
Surveyor's Michigan License No. 37279

