

FEB 24 2000

SECTION

OTTAWA COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

99 OCT 27 PM 1:49

Greg Hinkley
REGISTER OF DEEDS
OTTAWA COUNTY, MICH.

For corners in Ottawa _____ (County)	Located in:	Corner Code #
1. Public Land Survey	T5N ___ R15W ___ T ___ R ___ T ___ R ___ T ___ R ___	B-5 _____ North 1/4 corner Section 18 Holland Twp.
2. Property Controlling in Section	S ___ T ___ R ___ S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___ S ___ T ___ R ___	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Steve Lampen _____, in a field survey on September 15, 1999, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5	18	17	16	15	14	13							
6													
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
 B-5 L.C.R.C. - L3, P341 - Clapp - 1979
 GLO - Brookfield - 1832 Found 1/2" steel bar
 Set 1/2 mile post NE corner garage SW 72.55
 Butternut 20 N 65 E 99 8" Ash NW 41.10
 Elm 10 S 70 E 69 SW corner concrete bridge deck SE 32.95

L.C.R.C. - L1, P251 - Greer - 1971
 Found T iron
 SE corner of SE wingwall E 29.05
 W culvert wingwall N 5.2
 NE corner of garage SW 72.55

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 B-5 Found 1/2" steel bar NE corner garage SW 72.55 8" Ash NW 41.10

This corner was set on line between C-5 and M-5, T5N, R16W Measure the 1/2" iron to be 0.33 South of C-5 to M-5 M-5, T5N, R16W, is 32.47' South of A-5, T5N, R15W

Replaced steel bar with an Ottawa County Remonumentation iron and cap in a set monument box and accepted it as the best position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 B-5 Ottawa County Remonumentation iron and cap in a monument box
 Azimuth = Michigan State Plane grid direction

Chiseled "+", top step, NE concrete wingwall	76° 01'	84.06
Chiseled "+", top step, SE concrete wingwall	111° 47'	60.19
Remonumentation tag in E side twin 8" Ash	349° 07'	41.00
Hydrant, top, centerline	306° 11'	56.77
NE corner garage foundation	203° 09'	72.48

10/18/99

SL

Signed by Steven Lampen Date OCTOBER 25, 1999

Surveyor's Michigan License No. 37279

