

FEB 24 2000

SECTION

OTTAWA COUNTY REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

99 OCT 27 PM 1:48

*Greg Schaller*  
REGISTER OF DEEDS  
OTTAWA COUNTY, MI

For corners in

Ottawa  
(County)

Located In:

Corner Code #

- 1. Public Land Survey T5N R15W  
T R  
T R  
T R
- 2. Property Controlling S T R  
in Section S T R
- 3. Miscellaneous S T R  
Property in Sec. S T R

B-11  
North 1/4 corner  
Section 31  
Holland Township

Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

I, Steve Lampen, in a field survey on September 14, 1999, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

B-11	Peck - 1890's	B-11 is shown on unrecorded survey by W & W in 1972
GLO - Brookfield - 1832	Iron stake	
Set 1/2 mile post	B-11 to C-11 = 2652.5	
Beech 10 N 42 W 24	B-11 to B-13 = 5286.5	LCRC - L2, P425 - Englert - 1973
Beech 6 S 64 E 13		Found 2" square iron
	B-11 is shown on Plat of Diekema Homestead Addition by Peck - 1906	SE power pole 37.00
		NE telephone pole 32.40
		SW crossbuck 60.85

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

B-11 Found 1/2" iron in monument box  
B-11 to C-11 - Peck = 2652.5 meas. = 2652.72 B-11 to B-13 - Peck = 5286.5 meas. = 5286.61  
Found 1/2" iron is at the position of the 2" square iron and fits the monumentation of Diekema Homestead Addition, the unrecorded W & W Survey and many other plats and surveys.

Replaced 1/2" iron with an Ottawa County Remonumentation iron and cap and accepted it as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

B-11 Ottawa County Remonumentation iron and cap in monument box.  
Azimuth = Michigan State Plane grid direction

NW corner concrete block building	128° 40'	74.15
NE corner brick building	197° 46'	184.61
SE corner building, stucco	307° 46'	73.96
SW corner gate base, concrete	344° 14'	75.58
Remonumentation tag SE side Power pole	53° 28'	34.06
NGS BM 3 319	201° 41'	182.29

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11	31	32	33	34	35	36							
12													
13													

9/20/99  
*YDP*

Signed by Steven Lampen

Date OCTOBER 18, 1999

Surveyor's Michigan License No. 37279



Receipt #61757