

SURVEY & REMONUMENTATION

APR 25 1995

COMMISSION

OTTAWA COUNTY REMONUMENTATION

RECORDED

LAND CORNER RECORDATION CERTIFICATE 94 DEC -8 PM 12:33
Filing Requirement of Act 74, Mich. P.A. 1970

Four corners in OTTAWA

Richard C. Callman
REGISTER OF DEEDS
OTTAWA COUNTY, MI

(County)	Located In:		Corner Code #
Public Land Survey	T	5N 15W	C-7 (SE cor Section 18)
	T		Holland Twp
	T		
	T		
Property Controlling in Section	S		
	S		
Miscellaneous Property in Sec.	S		
	S		

Register of Deeds Stamp & File Number

Lot No. _____, Recorded Plat _____
Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

Randal J. Vugteveen, in a field survey on November 14, 1994, hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

Description of original monument and accessories and/or subsequent restoration:
C-7 common corner to Sections 17, 18, 19 & 20

1832 - Brookfield	Liber 1, Page 787	Liber 5, Page 116
Set post	Find Iron bar (1972 JPC)	CIM
1. Ash 17" S85W 40 Links	10" Oak SW 71.65'	PP SE 58.58
2. Ash 18" N62E 57 Links	Power Pole NW 36.50'	8" Tree SW 70.71
	10" Twin Maple NE 78.25'	PP NW 60.09
	Guy Pole SE 35.44'	9" Cedar NE 85.63


Description of corner evidence found and/or method applied in restoring or reestablishing corner:
C-7 Found broken CIM at centerline "X" of 136th & James st. and accepted as a careful and faithful perpetuation of the position of the original corner

Light pole S28E 58.70'	10" Oak SW 71.65'
Nail NW side of 9" Cedar N50E 85.62'	

P.A. 345 OTTAWA COUNTY
PEER APPROVED 11/21/94
Murray D. Nedewold

Description of monument for corner and accessories established to perpetuate locating the position of the corner:
C-7 Cast Iron Monument in Mon Box

- Top hydrant N38E 52.57'
- Set Ottawa County Remon Tag & Nail in NW side 10" Cedar N50E 85.60'
- Set Ottawa County Remon Tag & Nail in SW side 36" Twin Oak S44E 84.65'
- Set Ottawa County Remon Tag & nail in SE side 12" Gum Tree S50W 72.20'
- Set Ottawa County Remon Tag & Nail in W side P. pole N25W 60.18'



Signed by *Randal J. Vugteveen*
Surveyor's Michigan License No. 28429

Date Nov. 21, 1994