

SURVEY & REMONUMENTATION

DEC 01 1998

SECTION

**OTTAWA COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

RECORDED
98 MAR 16 PM 12:37

For corners in

OTTAWA

(County)

Located In:

Corner Code #

1. Public Land Survey

T 5N R 15W

D-13 (S 1/4 cor

T _____ R _____

Section 32) Holland

T _____ R _____

Twp _____

T _____ R _____

2. Property Controlling in Section

S _____ T _____ R _____

S _____ T _____ R _____

3. Miscellaneous Property in Sec.

S _____ T _____ R _____

S _____ T _____ R _____

Gary [Signature]
REGISTER OF DEEDS
OTTAWA COUNTY, MI

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Randal J. Vugveen, in a field survey on December 3, 19 96 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

D-13 Common corner to Section 32

1831 - Lyon

Set HMP

8" Sugar N87°E 25 Links

6" Beech N43° W 37 Links

SW corner Sec. 32 W. 2644.3' Co. Surveyor E.H. Peck 1899
SE cor. Sec. 32 E. 2641' Co. Surveyor E.H. Peck 1899
Center Sec. N. 2639' Co. Surveyor E.H. Peck 1899
D - 1 Allegan Co. W. 19.40' Liber 2, Page 100

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

D-13 Found iron bar with Ottawa County Remon Cap East of centerline Central Avenue & on centerline E 32nd St.

SW cor. Sec. 32, W. 2645.86'

SE cor. Sec. 32 E. 2642.19'

Center Sec. 32 N. 2639.05'

Checks with existing plats @ Central & 32nd

D-1 Allegan Co. W. 19.40'

Accepted iron bar with Ottawa County Remon cap as a careful perpetuation of the position of the original corner

Set monument box around cap & rewitnessed

P.A. 345 OTTAWA COUNTY
PEER APPROVED 12/1/97

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D-13 Iron bar with Ottawa County Remon Cap in monument box

NE corner brick house #8 W 32nd St. AZ 228° 106.36'

Set Ottawa County Remon tag & nail in N side 14" Twin Maple AZ 128° 55.98'

Most Westerly Southwest corner brick church AZ 48° 151.21'

Set Ottawa County Remon tag & nail South side 14" Maple AZ 292° 60.18'

Red Cap in monument box AZ 270° 19.40' (Allegan Corner)

Centerline of road to North West 0'

On centerline of East-West road

NOTE: (see sketch on back)

Signed by Randal J. Vugveen

Surveyor's Michigan License No. 28429

Date Dec. 1, 1997



