

SURVEY & REMONUMENTATION

OTTAWA COUNTY REMONUMENTATION

RECORDED

APR 25 1995

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

94 DEC -8 PM 12:33

COMMISSION

Phyllis Kallman
REGISTER OF DEEDS
OTTAWA COUNTY, MI

For corners in OTTAWA

	(County)	Located in:	Corner Code #
1. Public Land Survey	T <u>5N</u> R <u>15W</u>	E-6 (E 1/4 cor of Section 17)	Holland Twp
	T _____ R _____		
	T _____ R _____		
	T _____ R _____		
	T _____ R _____		
2. Property Controlling in Section	S _____ T _____ R _____		
	S _____ T _____ R _____		
3. Miscellaneous Property in Sec.	S _____ T _____ R _____		
	S _____ T _____ R _____		
4. Lot No. _____, Recorded Plat _____			
5. Private Claims _____			

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	13	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

Randal J. Vugteveen, in a field survey on November 14, 1994

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

E-6 common corner to Sections 16 & 17

1832 - Brookfield
Set post
Hemlock 24" N60E 21 Links
Locus 24" S75W 22 Links

Liber 1, Page 125
PP NW 60.33 / PP NE 95.42' / SE house corner W 63.43' / NE house corner SW 93.14'

Liber 1, Page 261
Found iron Pipe
Set cast iron mon
SE house corner W 63.43' / NE house corner SW 93.14' / PP NW 60.33' / PP NE 95.42'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
E-6 Found broken CIM in front yard of House #2809 on centerline Felch extended and centerline 128th extended and accepted as a careful and faithful perpetuation of the position of the original


Cast mon | PK nail in W side P. pole N31E 96.00'
Nail & Tag #14091 in E side 28" Oak N22E 88.43' | Nail & Tag #16042 S side P. pole N34W 60.26'

NE house corner SW 93.14'

P.A. 345 OTTAWA COUNTY
PEER APPROVED 11/21/94
Randal J. Vugteveen

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
E-6 Cast Iron Monument

SE corner house #2809 N83W 63.25'
NE corner porch foundation N58W 60.81'
NE foundation corner house #2799 S53W 93.28'
Set Ottawa County Remon Tag & Nail in W side P. pole N31E 96.00'
Set Ottawa County Remon Tag & Nail in E side 28" Oak N22E 88.46'



Signed by *Randal J. Vugteveen*

Date Nov 21, 1994

Surveyor's Michigan License No. 28429