

**OTTAWA COUNTY REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Ottawa _____ (County)	Located In:	Corner Code #
1. Public Land Survey	T5N R15W	E-9
	T _____ R _____	NE cor. Sec. 29
	T _____ R _____	Holland Twp.
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

**RECORDED**  
96 DEC 20 PM 12:20  
*Register of Deeds Stamp & File Number*  
REGISTER OF DEEDS  
OTTAWA COUNTY, MI

I, Steven Lampen \_\_\_\_\_, in a field survey on December 9, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**  
E-9 LCRC Liber 4, Page 172 - 1981 - found gas pipe and wood  
GLO - Brookfield - 1832 stake, set cast iron monument  
Set corner in marsh to Centerline hydrant ENE 517.9'  
Sections 20, 21, 28 and 29 Centerline hydrant NNE 376.7'  
Red Oak 18 N 89 E 14.91' SW face of Windmill DeZwaan NE 579.6'


E-9 is shown on original Plat of Holland - 1848  
E-9 is shown as a gas pipe, 2649' North of E-10 on Survey by E. H. Peck - 1900±

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**  
E-9 Southwest face of Windmill DeZwaan NE 579.6'  
Found gas pipe and wood stake in 1981, 2650.7' North of E-10, replaced with cast iron monument. Found cast iron monument lying down in 1996, replaced with Ottawa County Remonumentation iron and cap and is accepted as a careful and faithful perpetuation of the position of the original corner.

PEER APPROVED 12-9-96  
*M.D.N.*

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**  
E-9 Ottawa County Remonumentation iron and cap. Azimuth = Michigan State Plan grid direction

NW corner SW pillar on Windmill DeZwaan	50° 58'	578.88'
Hydrant, Top, centerline	64° 59'	519.7'
Hydrant, top, centerline	9° 09'	381.44'
Centerline water valve	63° 06'	489.43'



4 9.00 CORNER

Signed by Steven Lampen Date DECEMBER 13, 1996  
Surveyor's Michigan License No. 37279

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971  
REVISED MAY 14, 1975  
REVISED JAN., 1983  
ADAPTED FOR WORD PROCESSING MARCH, 1993