

**OTTAWA COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE**
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Ottawa</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T 5N R 15W	E-10
	T R	East 1/4 corner
	T R	Section 29
	T R	Holland Twp.
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

RECORDED

96 DEC 20 PM 12:20

Phyllis Holman
REGISTER OF DEEDS
OTTAWA COUNTY, MI

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Steven Lampen, in a field survey on December 6 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

E-10	LCRC I2 P51-	
GLO-Brookfield-1832	Fire hydrant	NE 46.65
Set 1/2 mile post	Guy pole	SE 47.85
Beech 10 N24W 20	P.P.	SW 49.98
do 10 S44E 5	P.P.	NW 45.63

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-10 Found iron pipe over FSB in monument box at the centerline intersection of 8th Street and Lincoln Ave. This corner fits the monumentation of the plats of the Original Plat of Holland, Subdivision of Block A, A.C. Van Raalte Addition No. 1, and Riverside Addition. This corner also agrees with section measurements by E.H. Peck taken about 1900.

Replaced iron pipe and steel bar with Ottawa County Remonumentation Iron and Cap and is accepted as a careful and faithful perpetuation of the position of the original corner.


P.A. 345 OTTAWA COUNTY
PEER APPROVED 12-9-96

S.D.N.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-10 Ottawa County Remonumentation Iron and Cap in monument box.
Azimuth = Michigan State Place Grid Direction

NE corner building, brick	215°42'	103.25
SE corner depot, brick, 4' above ground	50°59'	319.62
SW corner depot, brick, 4' above ground	46°36'	315.14
NW corner building, brick, 4' above ground	103°25'	175.56
SW corner building, brick	130°06'	221.56
NW corner building, brick	171°14'	236.05
SE corner building, brick	290°12'	151.09



\$ 9.00 CORNER

Signed by Steven Lampen Date DECEMBER 13, 1996

Surveyor's Michigan License No. 37279

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1976
REVISED JAN., 1983
ADAPTED FOR WORD PROCESSING MARCH, 1983