

**SURVEY &  
REMONUMENTATION**

APR 05 1996

OTTAWA COUNTY REMONUMENTATION

COMMISSION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in  
OTTAWA  
(County)

	Located In:	Corner Code #
1. Public Land Survey	T5N R15W	G-10 (E 1/4 cor Section 28) Holland Twp.
	T ___ R ___	
	T ___ R ___	
	T ___ R ___	
2. Property Controlling in Section	S ___ T ___ R ___	
	S ___ T ___ R ___	
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	
	S ___ T ___ R ___	

RECORDED

95 NOV 15 PM 2:09

*D. J. ...*  
REGISTER OF DEEDS  
OTTAWA COUNTY, MI

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Randal J. Vugteveen, in a field survey on October 17, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

**A. Description of original monument and accessories and/or subsequent restoration:**

G-10 Common corner to Sections 27 & 28

1832 - Lyon	Liber 5, Page 265	Liber 1, Page 275
Set 1/2 mile post	Set O.C. cast mon	Found angle iron
Hemlock N73 W12 7 Links	NW 50.62' nail & tag NE side pp	Twin 16" Willow SW 71.07'
Hemlock S76 E13 7 Links	NE 43.00' centerline top of hydrant	Support pole SE 37.92'
	SE 49.14' PK NE side of guy pole	12" Catalpa NE 64.44'
	SW 68.84' PK NE side of PP	C/L hydrant NE 42.90'
		Spike in PP NW 41.45'

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

G-10 Found OCRM cap in mon box @ centerline "X" E 8th St. & Waverly Ave 2' W of centerline "X" and accepted as a careful and faithful perpetuation of the position of the original corner


NW 50.62' nail & tag NE side pp	Found angle iron
NE 43.00' centerline top of hydrant	Twin 16" Willow SW 71.07'
SE 49.14' PK NE side of guy pole	Support pole SE 37.92'
SW 68.84' PK NE side of PP	12" Catalpa NE 64.44'
	C/L hydrant NE 42.90'
	Spike in PP NW 41.45'

P.A. 345 OTTAWA COUNTY  
PEER APPROVED 10/23/95  
*Randy D. McDowell*  
RD

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

G-10 Cast Iron Monument in mon box

Found Ottawa County Remon Nail & Tag in SE side p. pole Az. 201 deg 69.47'  
Found Ottawa County Remon Nail & Tag in W side 24" Maple Az. 149 deg 141.92'  
SW corner brick building #175 Waverly Az. 40 deg 193.75'  
Set Ottawa County Remon Nail & Tag in E side p. pole Az. 326 deg 50.48'



Signed by *Randal J. Vugteveen* Date Oct 20, 1995  
Surveyor's Michigan License No. 28429