SECTION

OTTAWA COUNTY REMONUMENTATION

RECORDED

LAND CORNER RECORDATION CERTIFICATE

99 OCT 27 PM 1:48

1

Filing Requirement of Act 74, Mich. P.A. 1970

	rining nequ	iteriterit of Act 14, Mich. F.A.	1370
For corners in Ottawa (County)	Located In:	Corner Code #	REGISTER OF DEEDS
Public Land Survey	T5NR15W TR T R	G-12 West 1/4 corner	
Property Controlling in Section	T R S T R	Section 34 Holland Township	
3. Miscellaneous Property in Sec.	S T R S T R		Register of Deeds Stamp & File Number
4. Lot No, 5. Private Claims	Recorded Plat		1 A B C D E F G H I J K L M
I, Steve Lampen do hereby certify that under	, in a field survey of requirements of P.A. 74, Michigan	on September 14, 19 99, P.A. of 1970, the corner points mention	2 6 5 4 3 2 1 3 4 7 8 9 10 11 12
in lines 1 and 2 above we current manual of survey in Management or by a decree above were in conformance	re in conformance with regulations structions of the United States De of a Court of Law and/or that the with the rules of the Michigan Bo	s and rules therefore as required in partment of the Interior, Bureau of La corner points mentioned in lines 3, 4 an ard of Land Surveyors or by a Decree of	the nd 6 18 17 16 15 4 13 df 5 7 of a
expressed below:		re-monumented, recovered, found	as 9 10 30 29 28 27 26 25
on this certifica			11 12 31 32 33 9 34 35 36
		s and/or subsequent restoration:	13
G-12 GLO - Brookfield - 183	LCRC, L2, P29 - Clay	· • · · · · · · · · · · · · · · · · · ·	B5 - Brintnall - 1987
Set 1/2 mile post	32 Found monument box Power pole NW 35.90		ned iron, set C.I.M. orner transformer box
Sugar 4 S 79 E 16	Power pole NE 42.50		end top C+G rad.
Sugar 14 S 69 W 23	Guy nole SW 35 30		end ton CLC tad

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 G-12 Found cast iron monument in monument box.
 NE 59.01 PK SE side power pole, SW 47.31 tag SE side power pole

Centerline street sign SE 47.0

Found cast iron monument fits the monumentation of many surveys and is accepted as a careful and faithful Perpetuation of the position of the original corner.

> P.A. GOS DITAMO CARA e ditte or en jarry.

NE 59.01 PK SE side power pole

SW 47.31 tag in SE side power pole

NW 49.48 PK in top C+G

Э.	Description of monument for corner and accessories established to perpetuate locating the position of the corner:
	Cast iron monument in monument box

Azimuth = Michigan State Plan grid direction

Ren	nonument	tation tag	in SE side power pole	37°	52 °	59.13
Rer	nonument	tation tag	in SE side power pole	213°	39'	47.66
SE	corner	building,	concrete block	299°	32'	124.40
SE	corner	building,	wood	220°	19'	75.28
SE	corner	building,	brick	192°	49.	224.22
NW	corner	building,	brick	240°	24'	114.82



Date OCTOBER 16, 1999