

SURVEY & REMONUMENTATION

DEC 01 1998

Ottawa County Remonumentation
LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

99 MAY 22 PM 4: 06

SECTION

For corners in

<u>Ottawa</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>5N</u> R <u>15W</u>	H-1 (N $\frac{1}{2}$, 3) Holland Twp.
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Long
 REGISTER OF DEEDS
 OTTAWA COUNTY, MI

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, John C. Bueche, in a field survey on March 19, 19 98, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

H-1 GLO
 Did not set corner
 LCRC L1, P583, Aug., 1972
 Set cast iron mon.
 S 1/4 cor. Sec. 34 Olive Twp. W 61.93'
 PP S 82.18'
 C/L st. sign WSW 69.40'
 Fence to South

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

H-1 Found 1/2" rerod 0.04' West of East edge of Mon. Box & 0.60' North of Township Line H-13 (S 1/4 34) & I-13 (SE 34) 6-15 on C/L bit. road N & S; on field division South (No cover)
 PP S 82.18'±
 Olive Twp. cor. W 61.93'±

This position not established by original government surveyors.
 This monument is accepted as the best available evidence of the position of the corner.

PEER APPROVED 4/20/98
[Signature]

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H-1 Set 3/4" x 24" pin with Ottawa Co. Cap on Township Line
 Ottawa Co. Remon. Tag & Nail in NE side PP N 55° W 148.13'
 Ottawa Co. Remon. Tag & Nail in W side PP South 83.10'
 NE cor. wood siding of bldg. S 65° W 240.26'
 NW cor. wood siding of bldg. S 43° W 140.26'
 NE cor. wood siding of bldg. S 21° W 109.57'
 Set PK South & East 1.00'
 On C/L bit. road E-W; on field division South
 Ottawa Co. Mon. in Mon. Box West 61.96' H-13 (S 1/4 34, 6-15)
 1/2" rerod in Mon. Box North 0.60'



\$ 11.00 CORNER
 \$ 2.00 PHOTO

Signed by John C. Bueche Date 4-1-98
 Surveyor's Michigan License No. 13027

SURVEY &
REMONUMENTATION

DEC 01 1998

SECTION

