

FEB 24 2000

OTTAWA COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED
99 OCT 27 PM 1:49

SECTION

For corners in
Ottawa
(County)

Located in:

Corner Code #

- 1. Public Land Survey T5N R15W 1-2
T R
T R West 1/4 corner
T R Section 2
- 2. Property Controlling S T R
in Section S T R Holland Township
- 3. Miscellaneous S T R
Property in Sec. S T R

Ray Schiller
REGISTER OF DEEDS
OTTAWA COUNTY MI

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, Steve Lampen, in a field survey on September 15, 1999, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

I-2 GLO - Brookfield - 1832 Set 1/2 mile post Beech 22 N 7 E 19 Beech 4 N 65 W 32	LCRC, L1, P25 - Clapp -1971 Set steel bar at measurement Pro-rated against G.L.O. Recorded distance, but not on a straight line Telephone pole SW 27.27 Power pole SE 73.28 30" Ash NE 62.95	LCRC, L5, P134 - Englert - 1984 Found steel bar, set C.I.M. 30" Ash NE 64.29 8" Ash E 33.52 Power pole ESE 73.73 4" Ash WNW 50.13
---	---	--

80.75 N boundary 1.10
East of post and set corner

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-2 Found cast iron monument in monument box in centerline road intersection
Power pole SE 73.28

I-2 to I-1 meas. 2703.55, GLO pro-rate = 2703.33
I-2 to I-3 meas. 2653.36, GLO pro-rate = 2653.58
I-2 is 72.6' E of a straight line between I-1 and I-3
The occupation lines 1/4 mile E and W fit the section subdivisions using the cast iron monument as I-2
Accepted the cast iron monument as the best position of the corner.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

OTTAWA COUNTY
10/18/99
[Signature]

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-2 Cast iron monument in monument box
Azimuth = Michigan State Plane grid direction

Hydrant, top centerline	143° 45'	49.10
Hydrant, top centerline	170° 27'	157.68
EK and washer in S side power pole	116° 16'	73.77
NW corner porch foundation	213° 26'	312.10
Occupation line towards the E	0°	4



Signed by Steven Lampen

Date OCTOBER 25, 1999

Surveyor's Michigan License No. 37279