

DEC 01 1993

COMMISSION

OTTAWA COUNTY REMONUMENTATION

RECORDED

93 NOV 11 AM 11:54

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

REGISTER OF DEEDS
OTTAWA COUNTY, MI

For corners in OTTAWA

Form with fields for 'Located In:' (5N 15W), 'Corner Code #', and numbered sections 1-5 for recording details.

Register of Deeds Stamp & File Number

Grid table with columns A-M and rows 2-13, containing numerical values and a central marker.

I, Randal J. Vugteveen, in a field survey on September 16, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration: I-3 corner common to Sections 2, 3, 10 & 11


Table with 3 columns listing monument details: LCRC Liber 1, Page 27; R.R. Spike; Nail in P. Pole SE 53.42' / Nail in P. Pole NE 52.24' / Nail in T. Pole SW 57.38' / Centerline St. sign NW 35.39'; LCRC Liber 3, Page 155; R.R. Spike; P. Pole SE 53.94'; P. Pole NE 52.30'; Guy Pole SW 38.18'; 12" Maple SW 68.77'; LCRC Liber 5, Page 138; Cast Iron Monument; P. Pole NE 52.30'; P. Pole SE 54.04'; Guy Pole SW 38.22'; 15" Poplar NW 72.44'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner: I-3 Found cast iron monument in mon. box at centerline "X" of 112th & Quincy and accepted as a careful and faithful perpetuation of the position of the original corner

Found PK & tag in E side P. Pole S45E 53.84' / Found PK & tag in NW side P. Pole N37E 52.27'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner: I-3 Set Ottawa County Remon Cap on 5" X 3/4" pipe over monument cemented in mon box

- Set Ottawa County Remon Tag & Nail in E side 16" Maple S23W 68.68'
Set Ottawa County Remon Tag & Nail in W side P. Pole S45E 53.81'
Set Ottawa County Remon Tag & Nail in E side 14" Pine S45E 76.10'
Set Ottawa County Remon Tag & Nail in NW side P. Pole N37E 52.32'
Set Ottawa County Remon Tag & Nail in W side 24" Poplar N40W 72.29'



Signed by Randal J. Vugteveen Date Nov 5, 1993
Surveyor's Michigan License No. 28429