

SURVEY & REMONUMENTATION

RECORDED

APR 24 1995

OTTAWA COUNTY REMONUMENTATION

94 DEC 14 AM 9:41

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Richard R. Williams
REGISTER OF DEEDS
OTTAWA COUNTY, MI

COMMISSION
For corners in
OTTAWA
(County)

Located In: Corner Code #

- | | | |
|------------------------------------|------------------------|---------------------|
| 1. Public Land Survey | <u>15N</u> <u>R15W</u> | <u>I-9 (SE cor</u> |
| | T ___ R ___ | <u>Section 22)</u> |
| | T ___ R ___ | <u>Holland Twp.</u> |
| | T ___ R ___ | _____ |
| 2. Property Controlling in Section | S ___ T ___ R ___ | _____ |
| | S ___ T ___ R ___ | _____ |
| 3. Miscellaneous Property in Sec. | S ___ T ___ R ___ | _____ |
| | S ___ T ___ R ___ | _____ |

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Randal J. Vugteveen, in a field survey on December 7, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

I-9 Common corner to Sections 22, 23, 26 & 27

1832 - Brookfield	Liber 1, Page 579	Liber 4, Page 171
Set corner	Found boat spike	4" cast iron pipe w/cap stamped "Ottawa CO
Hemlock 3" N72W 4 Links	P. Pole NE 108.72'	SEC COR" / S40E 39.20' 17" Maple / N17E
Lynn 30" S72E 28 Links	P. pole SW 35.70'	14.55' 8" Poplar / N75E 18.17' 4" Ch Elm /
	Centerline St. sign SE 42.34'	N20W 127.0' P. pole / S15E 103.5' 8" Pine
	15" Basswood WSW 82.70'	/ South 36.0' Fence post (2nd from East
		end)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-9 Found CIM 465' North of centerline "x" Legion Park Drive and Country Club Road and accepted as a careful and faithful perpetuation of the position of the original corner

- S40E 39.20' 17" Maple
- N17E 14.55' 8" Poplar
- N20W 127.0' P. pole
- S15E 103.5' 8" Pine
- S 36.0' fence post (2nd from East end)


P.A. 345 OTTAWA COUNTY
PEER APPROVED 12/12/94
Randal J. Vugteveen

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-9 Cast Iron Monument

AZ = Michigan State Grid Direction

- Set Ottawa County Remon Tag & Nail in W side 18" Poplar AZ. 10 deg 14.35'
- Set Ottawa County Remon Tag & Nail in N side 30" Maple AZ. 140 deg 39.40'
- Set Ottawa County Remon Tag & Nail in E side P. pole AZ. 345 deg 126.71'
- Set Ottawa County Remon Tag & Nail in W side Gnarly 48" Willow AZ. 190 deg 55.96'



Signed by *Randal J. Vugteveen*
Surveyor's Michigan License No. 28429

Date Dec 12, 1994