

**SURVEY & REMONUMENTATION**

DEC 16 1996

**OTTAWA COUNTY REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in **COMMISSION**  
**OTTAWA**

(County)	Located In:	Corner Code #
1. Public Land Survey	T <u>5N</u> R <u>15W</u>	I-12 (E 1/4 cor Section 34) Holland Twp.
	T ___ R ___	___
	T ___ R ___	___
	T ___ R ___	___
2. Property Controlling in Section	S ___ T ___ R ___	___
	S ___ T ___ R ___	___
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	___
	S ___ T ___ R ___	___

**RECORDED**  
96 NOV 14 AM 11:19  
*Randal J. Vugteveen*  
REGISTER OF DEEDS  
OTTAWA COUNTY, MI  
**Register of Deeds Stamp & File Number**

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Randal J. Vugteveen, in a field survey on September 4, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	16		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

**A. Description of original monument and accessories and/or subsequent restoration:**

I-12 Common corner to Sections 34 & 35  
1832 - Lyon  
Set 1/2 mile post  
Sugar S70 E10 20 Links  
Sugar N55 W10 10 Links

Liber 8, Page 505  
1" Round Iron / Nail & Tag #14091 P. Pole SE 69.00'  
/ Nail in Maple SW 60.38' / Nail in P. Pole NW 49.68'  
/ Top of Hydrant NE 51.16'

Liber 8, Page 176  
Center hydrant NE 51.21' / P. Pole NE 68.96' / Nail  
in Maple SW 60.37' / P. Pole NW 49.65'

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

I-12 Found 1" solid bar in mon box 2' N of Mason St. & on centerline of Country Club Road and accepted as a careful and faithful perpetuation of the position of the original corner

Nail & Tag P. Pole SE 68.96' / Nail in 10" Maple SW 60.35' / Nail in P. Pole NW 49.65' / Top of hydrant NE 51.15'  
Center hydrant NE 51.15' / Nail in P. Pole SE 68.96' / Nail in 8" Maple 60.35' / Nail in P. Pole NW 49.65'


P.A. 345 OTTAWA COUNTY  
PEER APPROVED 10-21-96

*R. D. N.*

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

I-12 Removed 1" dia. pipe - Set 3/4" x 2' solid bar with Ottawa County Remon Cap in mon box

Center Top of Hydrant Az 41 deg 51.15'  
Set Ottawa County Remon Nail & Tag in NE side power pole Az 140 deg 68.95'  
Set Ottawa County Remon Nail & Tag in SE side 10" Maple Az 229 deg 60.35'  
Set Ottawa County Remon Nail & Tag in SW side power pole Az 310 deg 49.65'



Signed by *Randal J. Vugteveen*  
Surveyor's Michigan License No. 28429

Date SEPT 16, 1996

9.00  
1.00