

**SURVEY &
REMONUMENTATION**

DEC 16 1996

COMMISSION

**OTTAWA COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

<u>OTTAWA</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>5N</u> R <u>15W</u>	I-13 (SE 1/4 cor Section 34) Holland Twp.
2. Property Controlling in Section	T <u> </u> R <u> </u>	_____
3. Miscellaneous Property in Sec.	T <u> </u> R <u> </u>	_____
	S <u> </u> T <u> </u> R <u> </u>	_____
	S <u> </u> T <u> </u> R <u> </u>	_____
	S <u> </u> T <u> </u> R <u> </u>	_____
	S <u> </u> T <u> </u> R <u> </u>	_____

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

RECORDED
96 NOV 16 AM 11:19
Randal J. Vugteveen
REGISTER OF DEEDS
OTTAWA COUNTY, MI
Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Randal J. Vugteveen, in a field survey on September 4, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

I-13 Common corner to Sections 34 & 35 1832 - Lyon Set post Cherry N70 E67 7 Links Maple N62 W 77 7 Links	S 1/4 cor. Sec. 34 W 2637.52' HEI / S 1/4 cor. Sec. 35 E 2646.54 HEI / E 1/4 cor. Sec. 34 N 2636.13 HEI / I-1 Allegan Co. W 111.90 HEI
---	--

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-13 Found 3/4" pipe in mon box 2.5' N & 2' W of centerline "X" Ottogan St. & Country Club Rd. and accepted as a careful and faithful perpetuation of the position of the original corner
 S 1/4 cor. Sec. 34 W 2637.53' / S 1/4 cor. Sec. 35 E 2646.60' / E 1/4 cor. Sec. 34 N 2636.13' / I-1 Allegan Co. W 111.90'

P.A. 345 OTTAWA COUNTY
PEER APPROVED 10-21-96
J.D.N.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-13 Removed 3/4" pipe set 3/4" X 24" solid bar with Ottawa County Remon Cap in mon box
 Set Ottawa County Remon Nail & Tag in SW side power pole Az 313 deg 51.51'
 Set Ottawa County Remon Nail & Tag in SE side power pole Az 232 deg 43.14'
 Found capped iron 2' North of Iron in mon box (Allegan Cor I-1) Az 270 deg 111.90'
 Set Ottawa County Remon Nail & Tag in NW side corner fence post Az 49 deg 43.03'



Signed by *Randal J. Vugteveen*
 Surveyor's Michigan License No. 28429

Date Sept. 16, 1996