

SURVEY & REMONUMENTATION

OTTAWA COUNTY REMONUMENTATION

RECORDED

APR 25 1995

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

94 DEC -8 PM 12:32

COMMISSION

For corners in **OTTAWA**

Phyllis Robinson
REGISTER OF DEEDS
OTTAWA COUNTY, MI

	(County)	Located In:	Corner Code #
1. Public Land Survey	T	5N R 15W	K-3 (NE cor of Sec. 11) Holland Twp
	T	R	
	T	R	
	T	R	
2. Property Controlling in Section	S	T R	
	S	T R	
3. Miscellaneous Property in Sec.	S	T R	
	S	T R	

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Randal J. Vugteveen in a field survey on November 15, 1994

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
K-3 common corner to Section 1, 2, 11 & 12

1832 - Brookfield	Liber 1, Page 21	Liber 3, Page 96
Set corner	Nail in Power pole NE 65.35'	1/2" Steel Bar
Hemlock 12" is post	Centerline St. Sign SE 40.71'	Power Pole NE 65.85'
	Nail in guy pole SW 31.98'	Street Sign SE 40.70'
	NE corner house foundation SW 64.37'	Guy Pole SW 31.93'
		Har. Cor SW 64.50'


B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
K-3 Found 1/2" rod in mon box at centerline "X" of 104th & Quincy and accepted as a careful and faithful perpetuation of the position of the original corner

Nail & Tag in NW side P. ple #14091 N46E
65.85' / Street sign S43E 40.62' / NE
foundation corner house #3991 S47W 64.44'

PA. 345 OTTAWA COUNTY
PEER APPROVED 11/21/94
Geordy D. Medewald

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
K-3 Removed 1/2" rod set 3/4" X 24" solid rod in mon box with Ottawa County Remon Cap

Set Ottawa County Remon Tag & Nail in NW side P. pole N46E 65.85'
Set Ottawa County Remon Tag & Nail in South side 24" Maple N70E 72.45'
Set Ottawa County Remon Tag & Nail in NW side guide pole S47W 32.62'
Set Ottawa County Remon Tag & Nail in W side P. pole S7E 243.73'
SW foundation corner porch house #10391 N61E 110.48'
PK Nail N45W 2.87'



Signed by *Randal J. Vugteveen* Date Nov. 21, 1994
Surveyor's Michigan License No. 28429