

**SURVEY &  
REMONUMENTATION**

OTTAWA COUNTY REMONUMENTATION

RECORDED

APR 25 1995

LAND CORNER RECORDATION CERTIFICATE

94 DEC -8 PM 12: 32

COMMISSION

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in OTTAWA

*Reginald S. Robinson*  
REGISTER OF DEEDS  
OTTAWA COUNTY, MI

(County)	Located In:	Corner Code #
1. Public Land Survey	T <u>5N</u> R <u>15W</u>	K-7 (SE cor of Sec. 14) Holland Twp.
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Randal J. Vugteveen, in a field survey on November 15, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:  
K-7 common corner to Sections 13, 14, 23 & 24

1832 - Brookfield	Liber 1, Page 371
Set corner	Found iron pipe set cast iron mon.
Beech 3" S42E 4 links	20" Sycamore NE 35.99'
Locus 10" N48W 25 links	Power Pole SE 12.42'
	Telephone pole SE 59.65'
	Guy pole SW 72.38'
	SE cor SW bridge abutment NW 85.34'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
K-7 Found broken CIM 125' South of RR tracks 60' W of the river and 110' NE of James Street and accepted as a careful and faithful perpetuation of the position of the original corner


Sycamore stump NE 36'
Power Pole SE 12.80'
SE cor SW bridge abutment N13W 85.23'

P.A. 345 OTTAWA COUNTY  
PEER APPROVED 11/21/94

*Heddy D. Nedewell*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
K-7 Cast Iron Monument in Mon Box

Set Ottawa County Remon Tag & Nail in SW side 14" Ash N60W 70.69'
Set Ottawa County Remon Tag & Nail in N side big P.P. S68E 14.13'
Set Ottawa County Remon Tag & Nail in NW side 30" stump Sycamore N30E 36.28'
SE corner SW bridge abutment N13W 85.23'



Signed by *Randal J. Vugteveen*

Date Nov. 21, 1994

Surveyor's Michigan License No. 28429