

FEB 24 2000

OTTAWA COUNTY REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

99 OCT 27 PM 1:49

SECTION

For corners in

Ottawa  
(County)

Located In:

Corner Code #

- 1. Public Land Survey T5N R15W L-7  
T R  
T R  
T R  
North 1/4 corner  
Section 24  
Holland Twp.
- 2. Property Controlling S T R  
in Section S T R
- 3. Miscellaneous S T R  
Property in Sec. S T R

*Ray Schellton*  
REGISTER OF DEEDS  
OTTAWA COUNTY, MI

Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

I, Steve Lampen \_\_\_\_\_, in a field survey on September 15, 1999, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

1	A	B	C	D	E	F	G	H	I	J	K	L	N
2		6	5	4	3	2	1						
3													
4		7	8	9	10	11	12						
5													
6		18	17	16	15	14	13						
7													
8		19	20	21	22	23	24						
9													
10		30	29	28	27	26	25						
11													
12		31	32	33	34	35	36						
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- L-7 Bowen - 1926 L.C.R.C. 3 P 302 - Clapp - 1978  
GLO - Brookfield - 1832 Brass plug in concrete pavement Found 1 1/4" Steel bar  
1/4 section post on true line NW to Se corner filling station 75.5 Power pole NE 35.86  
Hemlock 10 N 14 E 27 SE 12" Maple 27.0 28" Maple NE 61.45  
Hemlock 10 S 15 W 19 NE 10" Maple 43.0 Power pole SE 43.97  
L-7 to M-7 = 2619 L-7 to M-7 = 2619 Power pole SW 31.80
- L.C.R.C. - L2, P83 - Roon - 1973 L.C.R.C. - L5, P290 - Greer - 1988  
Found brass plug Plug in concrete pavement  
24" Maple NE 49.15 NE corner brick house SE 93.23  
Top of hydrant NE 37.3 SE corner brick house NE 150.76  
Power pole SE 43.65 NW corner brick house SW 91.88  
Street sign centerline S 19.46 26" maple NE 61.62  
Power pole NW 70.12  
Centerline concrete pavement N 2.4

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

L-7 Found old brass plug in concrete pavement. Top of hydrant NE 37.3, street sign centerline S 19.46, power pole NE 35.86, power pole SW 31.80, hydrant NE 37.30, street sign S 19.46, NE corner brick house SE 93.23, SE corner brick house NE 150.76, NW corner brick house SW 91.88, 26" Maple NE 61.62, power pole NW 70.12 and centerline concrete pavement N 2.4

L-7 to M-7 Peck = 2620, Bowen = 2619, meas. = 2618.0

Found brass plug per the Zeeland Monument Map of 1926 by Carl Bowen and accepted it as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- L-7 Brass plug in concrete road pavement
- Azimuth = Michigan State Plane grid direction
- Remonumentation tag in N side power pole 291° 52' 70.11
- Survey tag #14091 in NW side 20" Maple 53° 35' 61.59
- SE corner house, brick 46° 54' 150.76
- SW corner house, brick 26° 07' 135.07
- NE corner house, brick 134° 29' 93.22
- NW corner house, foundation 235° 20' 91.85
- NE corner brick wingwall 323° 16' 123.52
- Hydrant, top centerline 45° 57' 37.26
- Centerline crack old concrete road pavement 0° 2.4

10/18/99  
*MDN*  
STATE OF MICHIGAN  
STEVEN LAMPEN  
LAND SURVEYOR  
NO. 37279  
REGISTERED LAND SURVEYOR  
Receipt #61757

Signed by Steven Lampen

Date OCTOBER 25, 1999

Surveyor's Michigan License No. 37279