

**SURVEY & REMONUMENTATION**

APR 24 1995

OTTAWA COUNTY REMONUMENTATION

RECORDED

94 DEC 14 AM 9:43

**LAND CORNER RECORDATION CERTIFICATE**

Filing Requirement of Act 74, Mich. P.A. 1970

*Register of Deeds*  
REGISTER OF DEEDS  
OTTAWA COUNTY, MI

COMMISSION  
For corners in OTTAWA

(County)	Located In:	Corner Code #
1. Public Land Survey	T <u>5N</u> R <u>15W</u>	M-4 (E 1/4 cor of Sec. 12) Holland Twp.
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

I, Randal J. Vugteveen, in a field survey on November 21, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

M-4 common corner to Section 12	Liber 2, Page 45	Liber 6, Page 5
1831 - Lyon & Sibley	Found 3/4" iron in centerline concrete /	Set CIM
Set H.M.P.	P. Pole SE 87.05' / "X" in pavement S	Nail NE side PP SE 87.05' / Nail S side 6"
Hemlock 7" N10"W 24 Links	64.30' / (Zeeland Twp Cor)	Oak Willow E 40.26' / NW cor house #3600
Ironwood 6" S42W 20 Links		ENE 100.98' / W 1/4 cor Sec. 7-5-14 S
		64.28'

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

M-4 Found CIM in mon box on centerline 96th Street and accepted as a careful and faithful perpetuation of the position of the original corner	CIM
P. pole SE 87.05'	Nail NE side P. pole 87.58'
	Nail S side 6" Oak Willow S77E 40.46'
	NW cor hse #3600 N77E 100.93'
	W 1/4 cor Sec. 7-5-14 S 64.28'

P.A. 345 OTTAWA COUNTY  
PEER APPROVED 12/12/94  
*Randal J. Vugteveen*

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

M-4 Cast Iron Monument in mon box


Set Ottawa County Remon Tag & Nail in NE side P. pole S36E 87.58'

SW brick corner house #3600 S66E 104.77'

NW brick corner house #3600 N77E 100.93'

Found CIM in mon box South 64.28'

Set Ottawa County Remon Tag & Nail in S side 8" Willow S77E 40.46'



Signed by *Randal J. Vugteveen* Date Dec 12, 1994

Surveyor's Michigan License No. 28429