

**OTTAWA COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE**
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED
97 JUL 24 PM 2:23

Edythe A. Adkinson
**REGISTER OF DEEDS
OTTAWA COUNTY, MI**

For corners in <u>Ottawa</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T5N R16W	F-1
	T R	N 1/4 corn. Sec. 4
	T R	Park Twp.
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Steven Lampen, in a field survey on December 6, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

F-1
GLO - corner not set by original GLO Survey
F-1 is not recorded

Survey in Liber 5, Page 183 - 1982
Found concrete monument Port Sheldon corner E 95.27'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

F-1
Found concrete monument Port Sheldon corner E 95.27'

This corner not monumented by the original GLO Survey. This monument is accepted as the best available evidence of the position of the corner.


Found concrete monument on the South line of Section 33, T6N, R16W, and replaced it with an Ottawa County Remonumentation iron and cap in a (set) monument box.

PA. 345 OTTAWA COUNTY
PEER APPROVED 12-9-96
S.D.N.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F-1
Ottawa County Remonumentation iron and cap in monument box. Azimuth = Michigan State Plan grid direction

F-13, T6N, R16W = iron in monument box	88° 24'	95.27'
Remon. tag in NE side 14" Pine	148° 22'	28.28'
Remon. tag in North side 16" Beech	251° 55'	60.10'
Remon. tag in East side 22" Oak	348° 15'	32.68'
Remon. tag in East side 12" Pine	198° 47'	21.47'
Centerline E and W asphalt road pavement	0°	0'
Centerline N and S asphalt road pavement (Lakeshore Ave.)	88° 24'	95.27'



Signed by Steven Lampen Date DECEMBER 13, 1996

Surveyor's Michigan License No. 37279