

SURVEY & REMONUMENTATION

APR 24 1995

**OTTAWA COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

RECORDED

94 DEC 16 AM 10:02

Phyllis Williams
REGISTER OF DEEDS
OTTAWA COUNTY, MI

For corners in **COMMISSION**

Ottawa (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>5N</u> R <u>16W</u>	<u>F-3 N1/4 Cor</u>
	T _____ R _____	<u>Sec 9</u>
	T _____ R _____	<u>Park Twp.</u>
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, John P. Clapp, in a field survey on December 3, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

F-3 Govt Land Office Survey Notes 1832-Surveyor, Calvin Britain Set 1/2 mile post 12" Red Oak N14°W 14 links 8" Sugar S25°W 10 links	F-3 Recorded in Liber 1, Page 289 Mar 8, 1972 Fd angle iron 36" Oak SE 25.70' Bldg Cor SE 24.30' NE Cor Well HseW 48.80' CL Lakeshore Rd E 108'	F-3 Recorded in Liber 2 Page 533, Aug. 12, 1974 Angle Iron NE Cor Blk Bldg S15°E 24.30' NE Cor Blk Bldg W 48.87' Power Pole N60°W25.45' SE Cor Blk Bldg N05°W46.90'
--	---	---

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

P.A. 345 OTTAWA COUNTY

BEER APPROVED 12/12/94

F-3
Found cast iron monument and accepted it as a careful and faithful perpetuation of the position of the original corner

Found P.K. in SE Side 18" Oak	AZ 125°	26.53'
NE Corner Concrete Brick Building	AZ 167°	24.34'
NE Corner Brick Well House	AZ. 269°	48.85'
Power Pole/Telephone Pole	AZ. 288°	25.46'
SE Corner Concrete Block Building	AZ. 353°	46.81'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F-3
Found Cast Iron Monument


O.C. Remon Tag & Nail SW Side 38" Oak	AZ. 125°	26.53'
O.C. Remon Tag & Nail SE Side 24" Oak	AZ. 225°	16.46'
O.C. Remon Tag & Nail SSW Side Power Pole	AZ. 288°	25.47'
O.C. Remon Tag & Nail in E Side 26" Beech	AZ. 357°	32.76'

(See reverse side for additional witnesses)

Signed by John P. Clapp

Date Dec. 6, 1994

Surveyor's Michigan License No. 14091



FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
RENEWED MAY 14, 1975
RENEWED JAN., 1983

00'E 1/2" S
 051 # 3000
 00'S 1/2" S
 051 # 3000

F-3

Additional Witnesses

NE Corner Concrete Block Building
 SE Corner Concrete Block Pump House
 NE Corner Concrete Block Pump House
 SW Corner Concrete Block Building
 SE Corner Concrete Block Building

AZ	195° 167°	26.53' 24.34'
AZ	265°	49.15'
AZ	269°	48.85'
AZ	293°	79.09'
AZ	353°	46.81'