

SURVEY & REMONUMENTATION

APR 24 1995

OTTAWA COUNTY REMONUMENTATION LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

94 DEC 14 AM 9:42

COMMISSION

For corners in

Robert R. Bellman
REGISTER OF DEEDS
OTTAWA COUNTY, MI

Ottawa (County) Located In: Corner Code ##

1. Public Land Survey	T <u>5N</u> R <u>16W</u>	<u>F-7 N1/4 Cor</u>
	T _____ R _____	<u>Sec 21</u>
	T _____ R _____	<u>Park Twp.</u>
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, John P. Clapp, in a field survey on December 1, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

<u>F-7 Govt Land Office Survey Notes</u>	<u>F-7 Recorded in Liber 2,</u>
<u>1832-Surveyor, Calvin Britain</u>	<u>Page 231 June 25, 1973</u>
<u>Set 1/2 mile post</u>	<u>Fd 1" iron pipe in CL Pavement</u>
<u>20" Beech S75°W 26 links</u>	<u>Fc Post SW 44.71'</u>
<u>16" Beech N61°E 21 links</u>	<u>St Sign W 23.50'</u>
	<u>18" Beech NW 38.78'</u>
	<u>TP NE 46.60'</u>
	<u>Iron N 33.00'</u>
	<u>Iron W 33.00'</u>

F-7 Recorded in Liber 5
Page 311, Mar. 18, 1988
Fd 1" pipe in CL Conc.
pavement in Mon Box
10" Maple SE 55.29'
18" Beech NE 68.86'
18" Beech NW 45.69'
10" Oak WNW 64.31'
14" Pine WSW 110.64'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

F-7
Found 1" iron pipe in monument box and accepted it as a careful and faithful perpetuation of the position of the original corner
Found Nail in NW Side F.C. Post AZ 226° 45.07'
Found Nail & Tag in SW Side 18" Beech AZ 308° 45.71'
Scar in E Side 12" Oak AZ 276° 64.21'


P.A. 345 OTTAWA COUNTY

PEER APPROVED 12/12/94

Robert R. Bellman

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F-7
Set O.C. Remon Iron and Cap in Monument Box
O.C. Remon Tag & Nail in W Side 40" Beech AZ 18° 147.77'
O.C. Remon Tag & Nail in NE Side 12" Maple AZ 131° 55.37'
O.C. Remon Tag & Nail in N Side 18" Pine AZ 253° 118.81'
O.C. Remon Tag & Nail in SW Side 18" Beech AZ 308° 45.72'



Signed by John P. Clapp

Date Dec. 5, 1994

Surveyor's Michigan License No. 14091

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983