

# SURVEY & REMONUMENTATION

APR 24 1995

COMMISSION

## OTTAWA COUNTY REMONUMENTATION LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

94 DEC 14 AM 10:02

*Rhonda Robinson*  
REGISTER OF DEEDS  
OTTAWA COUNTY, MI

For corners in

Ottawa  
(County)

Located in:

Corner Code ##

- |                                    |   |           |   |            |                       |
|------------------------------------|---|-----------|---|------------|-----------------------|
| 1. Public Land Survey              | T | <u>5N</u> | R | <u>16W</u> | F-9 (N1/4 Cor Sec 28) |
|                                    | T | _____     | R | _____      | Park Twp.             |
|                                    | T | _____     | R | _____      |                       |
|                                    | T | _____     | R | _____      |                       |
| 2. Property Controlling in Section | S | _____     | T | _____      | _____                 |
|                                    | S | _____     | T | _____      | _____                 |
| 3. Miscellaneous Property in Sec.  | S | _____     | T | _____      | _____                 |
|                                    | S | _____     | T | _____      | _____                 |
4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
5. Private Claims \_\_\_\_\_

Register of Deeds Stamp & File Number

John P. Clapp

November 30, 1994

I, John P. Clapp, in a field survey on \_\_\_\_\_, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

F-9	F-9	F-9
Govt Land Office Survey Notes Recorded in Liber 1, 1832-Surveyor, Calvin Britain	Page 225, Jan 11, 1972	Recorded in Liber 2, Page 153, May 22, 1973
Set Post	Fd Iron Pipe	Fd Ir Pipe Old County Witnesses
18" Beech S15°W 19 links	30" Maple NE 40.57'	24" Maple N30°E 40.58'
6" Beech N29°W 14 links	20" Maple SE 49.12'	18" Maple N45°W 35.45'
	15" Maple SW 42.85'	CL Fc. Post W 42.22'
	20" Maple NW 35.45'	14" Maple S30°W 42.85'
		20" Maple S70°E 49.10'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

F-9	Found iron pipe in monument box and accepted it as a careful and faithful perpetuation of the position of the original corner
Found Nail & Tag in SE Side 28" Maple	AZ 238° 53.91'
Found Nail & Tag in NE Side 20" Maple	AZ 136° 62.40'
Found Nail & Tag in NW Side 24" Maple	AZ 119° 49.07'
Found Nail & Tag in NE Side 16" Maple	AZ 217° 42.83'
Found scar in SE Side 20" Maple	AZ 305° 35.33'
CL Steel Fence Post	AZ 272° 42.21' ±

P.A. 345 OTTAWA COUNTY  
PEER APPROVED 12/12/94

*Richard P. Redwood*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F-9	Set O.C. Remon Cap & Iron in Monument Box
O.C. Remon Tag & Nail in SSW Side 36" Maple	AZ. 112° 66.06'
O.C. Remon Tag & Nail in SE Side 34" Maple	AZ. 21° 70.75'
O.C. Remon Tag & Nail in SW Side 20" Oak	AZ. 343° 134.46'
O.C. Remon Tag & Nail in SE Side 28" Maple	AZ. 238° 56.00'



Signed by John P. Clapp Date Dec. 2, 1994

Surveyor's Michigan License No. 14091