

# SURVEY & REMONUMENTATION

APR 24 1995

COMMISSION

OTTAWA COUNTY REMONUMENTATION  
 LAND CORNER RECORDATION CERTIFICATE  
 Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

94 DEC 14 AM 10:03

*Phyllis Robinson*  
 REGISTER OF DEEDS  
 OTTAWA COUNTY, MI

For corners in

Ottawa  
 (County)

Located In:

Corner Code #

- 1. Public Land Survey T 5N R 16W F-13 (S1/4 Cor Sec 33)  
 T \_\_\_\_\_ R \_\_\_\_\_ Park Twp.  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_
- 2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- 3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	16	17	18	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, John P. Clapp, in a field survey on November 30, 1994  
 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

- |  |   |
|--|---|
| <p><b>F-13</b><br/>                 Government Land Office Survey Notes, 1832,<br/>                 Surveyor, Lucius Lyon<br/>                 Set Post<br/>                 7" Maple N83E° 37 links<br/>                 10" Pine N31W° 1.21 chains<br/>                 (See reverse side for additional recordings)</p> | <p><b>F-13</b><br/>                 Common corner to F-1 in Allegan County. This corner is shown in and fits the monuments of Macatawa Park (Allegan &amp; Ottawa Co.) Liber 2, Page 12 &amp; 18 and the monuments of Heneveld's Supervisor's Resub of Macatawa Park (Ottawa Co.), Liber 9, Pages 32 &amp; 33. This corner was recorded in Liber 1, Page 809, Dec. 8, 1972<br/>                 Set CIM from ties and old plat<br/>                 40" Black Oak W 3.67' 30" Black Oak E 11.80'<br/>                 10" Chin. Elm SW 7.46' 6" Beech NE 11.65'</p> |
|--|---|

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner.


- F-13**  
 Found cast iron monument and accepted it as a careful and faithful perpetuation of the position of the original corner
- |                 |    |        |
|-----------------|----|--------|
| 40" Black Oak   | W  | 3.67'  |
| 30" Black Oak   | E  | 11.80' |
| 10" Chinese Elm | SW | 7.46'  |
| 6" Beech        | NE | 11.65' |

P.A. 345 OTTAWA COUNTY  
 PEER APPROVED 12/12/94

*Abdoy P. Heneveld*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- F-13**  
 Cast Iron Monument; Common Corner to F-1 in Allegan County
- |   |             |        |
|---|-------------|--------|
| O.C. Remon Tag & Nail S Side 42" Oak    | AZ. 245°48' | 4.59'  |
| O.C. Remon Tag & Nail E Side 8" Beech   | AZ. 09°27'  | 12.02' |
| O.C. Remon Tag & Nail N Side 6" Oak     | AZ. 94°52'  | 10.63' |
| O.C. Remon Tag & Nail W Side 16" Beech  | AZ. 181°41' | 30.87' |
| Found Tag & Nail #14091 S Side 16" Pine | AZ. 238°    | 56.35' |
| Found Iron Pipe Lot Corner              | AZ. 304°25' | 25.35' |



Signed by John P. Clapp *John P. Clapp* Date Dec 5, 1994  
 Surveyor's Michigan License No. 14091

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971  
 REVISION MAY 14, 1975  
 REVISED JAN., 1983

F-13

Recorded in Liber 4, Page 327

July 10, 1982

Found existing cast iron monument

40" B. Oak	W	3.67'
10" Chinese Elm	SW	7.46'
30" B. Oak	E	1.80'

1337  
# 057  
# 057  
# 057