

SURVEY & REMONUMENTATION

APR 05 1996

COMMISSION

**OTTAWA COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in
Ottawa _____
(County)

Located In: _____ Corner Code # _____

1. Public Land Survey T5N R16W G-2
T _____ R _____ (W 1/4 cor. Sec.
T _____ R _____ 3, Park Twp.)
T _____ R _____

2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

RECORDED
95 NOV 15 PM 2:08
D. Lyell
REGISTER OF DEEDS
OTTAWA COUNTY, MI
Register of Deeds Stamp & File Number

I, Steven Lampen _____, in a field survey on October 23 1995 _____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO Survey Notes 1832 Surveyor - Noah Brookfield Set 1/2 mile post 8" Maple N 83° W 3 links 8" Pine N 82° E 11 links	LCRC L 2-P331 1972 Found Iron bar 10" Maple NW 72.36' 30" Maple SE 59.95' Street sign SE 53.35' Power pole SW 35.87' 20" Cherry NE 75.03' 12" Cherry NW 68.78'	LCRC L 1-P 289 Found CIM Power pole SW 35.89' Power pole NE 139.11' 12" Tw. Cherry NW 68.80' 10" Maple MNW 72.27' 20" Cherry NE 74.87' 10" Oak ESE 79.90' 30" Maple SE 59.91'
--	--	--

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found CIM and is accepted as a careful and faithful perpetuation of the position of the original corner.

10" Maple NW 72.36'	Power pole SW 35.89'
30" Maple SE 59.95'	Power pole NE 139.11'
Power pole SW 35.87'	12" Tw. Cherry NW 68.80'
12" Cherry NW 68.78'	10" Maple MNW 72.27'
	30" Maple SE 59.91'

RA. 345 OTTAWA COUNTY
PEER APPROVED 10/23/95

Arvid P. Hedewell 9071

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

CIM	AZ = MI State plane grid direction
Remon. tag NW side 10" Oak	210° 00' 89.33'
Remon. tag SE side power pole	226° 47' 36.41'
Remon. tag NW side 34" Oak	125° 30' 61.23'
Remon. tag SE side 14" Oak	36° 33' 68.92'
Remon. tag SW side 20" Maple	336° 46' 72.85'



Signed by Steven Lampen

Date October 23, 1995

Surveyor's Michigan License No. 37279

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1976
REVISED JAN., 1983
ADAPTED FOR WORD PROCESSING MARCH, 1993