

OTTAWA COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

*Phyllis Kellman*  
REGISTER OF DEEDS  
OTTAWA COUNTY, MI

For corners in  
Ottawa

	Located In:		Corner Code #
	5N	16W	
1. Public Land Survey	T _____ R _____	G-5 (SW Sec 10)	
	T _____ R _____	Park Twp.	
	T _____ R _____		
	T _____ R _____		
2. Property Controlling in Section	S _____ T _____ R _____		
	S _____ T _____ R _____		
3. Miscellaneous Property in Sec.	S _____ T _____ R _____		
	S _____ T _____ R _____		

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

David R. Greer

September 15, 1993

I, \_\_\_\_\_, in a field survey on \_\_\_\_\_, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Recorded in Liber 1 Page 105

October 7, 1971

G-5

14" Maple	SW	65.05'
Power Pole	NW	43.60'
Support Pole	NE	40.42'
NE Cor C. Pillar	SW	45.57'

Recorded in Liber 1 Page 799

G-5 Dec. 8, 1972

Set C.I.M. in place of angle iron

Power Pole	NW	43.59'
Tele. Pole	NW	60.48'
Tele. Pole	NE	40.41'
CL St. Sign	SE	46.30'
18" Maple	WSW	59.88'
20" Maple	SSW	65.06'
NE Cor C. Pillar	SW	45.59'

Recorded in Liber 5, Page 312

Mar. 18, 1988

G-5

Cast Iron Monument

GP Tag No. 14091	NE	41.47'
8" Maple	SE	118.40'
4" Pine	NW	111.70'
8" Pine	NW	92.65'
Power Pole Face	NW	43.70'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-5

Found cast iron monument and accepted it as a careful and faithful perpetuation of the position of the original corner

GP Tag No 14091	NE	41.47'	Power Pole	NW	43.59'
8" Maple	SE	118.40'	Tele. Pole	NW	60.48'
4" Pine	SW	111.70'	Tele. Pole	NE	40.41'
8" Pine	NW	92.65'	CL Street Sign	SE	46.30'
Power Pole Face	NW	43.70'	20" Maple	SSW	65.06'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-5

Found C.I.M. in monument box

AZ - Michigan State Grid Direction

O.C. Remon tag & nail in W Side Power Pole	AZ.	206°11'	91.63'
O.C. Remon tag & nail in NE Side Power Pole	AZ.	140°32'	50.68'
CL Top of Hydrant	AZ.	313°19'	44.33'
O.C. Remon tag & nail in SW Side 10" Maple	AZ.	138°37'	126.66'
O.C. Remon tag & nail in NW Side 12" Pine	AZ.	42°17'	52.03'

Signed by

*David R. Greer*

Date

9/15/93

Surveyor's Michigan License No.

16042

