

SURVEY & REMONUMENTATION

APR 24 1995

COMMISSION

For corners in

OTTAWA COUNTY REMONUMENTATION LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

94 DEC 14 AM 10:02

Debra R. Robinson
REGISTER OF DEEDS
OTTAWA COUNTY, MI

<u>Ottawa</u> (County)	Located In:	Corner Code #:
1. Public Land Survey	T <u>5N</u> R <u>16W</u>	<u>G-6</u>
	T _____ R _____	<u>W1/4 Cor Sec 15</u>
	T _____ R _____	<u>Park Twp.</u>
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

John P. Clapp, in a field survey on November 29, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G-6 Govt Land Office Survey Notes 1832-Surveyor, Calvin Britain Set 1/2 Mile Post 20" Beech N54°W 15 links 10" Beech S26°E 16 links See reverse side for additional recordings (Liber 5, Page 130)	G-6 Recorded in Liber 1 Page 105, Oct 7, 1971 Found Iron 24" Maple W 31.35' 12" Pine SW 57.71' 20" Pine NW 39.80' Power Pole NE 60.45' NW Cor Hse SE 96.20'	G-6 Recorded in Liber 1 Page 431, Jun 9, 1972 Found Iron 24" Maple W 31.35' 12" Pine SW 57.71' 20" Pine NW 39.80' Power Pole NE 60.45' NW Cor. Hse. SE 96.20'
---	--	--

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-6 Found cast iron monument in monument box and accepted it as a careful and faithful perpetuation of the position of the original corner		
Found Nail in SW Side Power Pole	AZ 39°	60.39'
NW Corner House Foundation	AZ 105°	96.06'
CL Top of Hydrant	AZ 39°	49.77'
Found Nail SE Side Power Pole	AZ 39°	60.83'

Madon P. Newbold

P.A. 345 OTTAWA COUNTY

PEER APPROVED 12/12/94

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:


G-6 Found Cast Iron Monument in Monument Box		
O.C. Remon Tag & Nail SW Side 12" Pine	AZ. 323°	70.19'
O.C. Remon Tag & Nail NW Side 12" Pine	AZ. 59°	73.20'
SW Cor Concrete Porch to House #2820	AZ. 119°	101.14'
O.C. Remon Tag & Nail SE Side 12" Pine	AZ. 219°	69.44'

Signed by John P. Clapp

John P. Clapp

Date Dec 2, 1994

Surveyor's Michigan License No. 14091



FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, MAY 28, 1971
REVISED JULY 14, 1975
REVISED JAN., 1983

G-6
Recorded in Liber 5
Page 130, June 27, 1984
Found Iron
Set Cast Iron Monument
Power Pole NE 60.84'
10" Pine ENE 34.99'
27" Maple W 32.15'
8" Pine NW 63.88'

1984
JUN 27
11 30 AM
1984
JUN 27
11 30 AM