

SURVEY & REMONUMENTATION

APR 24 1995

COMMISSION

OTTAWA COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

94 DEC 11 AM 9:42

For corners in

<u>Ottawa</u> <small>(County)</small>	Located In:	Corner Code #:
1. Public Land Survey	T <u>5N</u> R <u>16W</u>	<u>G-10 W1/4 Cor</u>
	T _____ R _____	<u>Sec 27</u>
	T _____ R _____	<u>Park Twp.</u>
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Richard Robinson
REGISTER OF DEEDS
OTTAWA COUNTY, MI

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, John P. Clapp, in a field survey on November 18, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
G-10 Govt Land Office Survey Notes G-10 Recorded in Liber 1 G-10 Rec. in Liber 1
1832-Surveyor, Calvin Britain Page 127, Oct. 22, 1971 Page 365, May 11, 1972
Set Post Set Cast Iron Monument Fd Cast Iron Monument
10" Beech N42 °W 23 links in place of Conc. Monument 30" Maple NNW 65.28'
10" Beech S35 °E 15 links Power Pole W 16.14' Power Pole W 16.14'
30" Maple NW 26.57' 30" Maple NW 26.57'
30" Maple NNW 65.28' 24" Beech ENE 61.50'
24" Beech ENE 61.50' 18" Beech SE 57.55'
18" Beech SE 57.55'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-10
Found cast iron monument and accepted it as a careful and faithful perpetuation
of the position of the original corner
Found Nail & Tag in NW Side 22" Beech AZ 142° 57.52'


PA. 345 OTTAWA COUNTY
 PEER APPROVED 12/12/94

Richard Robinson

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-10
Cast Iron Monument
O.C. Remon Tag & Nail SE Side 18" Beech AZ. 46° 72.97'
O.C. Remon Tag & Nail SW Side 22" Beech AZ. 142° 58.25'
O.C. Remon Tag & Nail SE Side 12" Pine AZ. 227° 78.72'
O.C. Remon Tag & Nail NE Side Power Pole AZ. 319° 59.64'

Signed by John P. Clapp Date Dec 5, 1994
 Surveyor's Michigan License No. 14091



FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, MAY 14, 1975
 REVISED JAN., 1983