

SURVEY & REMONUMENTATION

APR 24 1995

COMMISSION

OTTAWA COUNTY REMONUMENTATION LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

94 DEC 14 AM 9:42

Register of Deeds
REGISTER OF DEEDS
OTTAWA COUNTY, MI

For corners in

<u>Ottawa</u> <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T <u>5N</u> R <u>16W</u>	<u>G-11 SW Cor.</u>
	T _____ R _____	<u>Sec 27</u>
	T _____ R _____	<u>Park Twp.</u>
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

I, John P. Clapp, in a field survey on November 22, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

G-11
Govt Land Office Survey Notes
1832-Surveyor, Calvin Britain
Set Post
12" Hemlock N12 °W 40 links
10" Hemlock N68 °E 30 links

G-11
Recorded in Liber 1
Page 127, Oct. 22, 1971
Set Cast Iron Monument in place of Concrete Monument
48" Oak NE 37.50' Power Pole SW 41.95'
Power Pole NW 56.13' CL St. Sign SE 39.00'
26" Oak NE 69.96' Cor Ch Lk Fn SE 48.41'
10" Tw Oak NW 66.26'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-11
Found steel bar in concrete and accepted it as a careful and faithful perpetuation of the position of the original corner.
Found Nail & Tag SE Side Power Pole NW 335° 56.18'
Found Nail & Tag NE Side Power Pole SW 217° 41.97'
CL Cor Chain Link Fence SE 140° 48.44'
SW Corner House Foundation NNE 32° 165.24'
NW Corner Brick House SE 140° 71.73'
NE Corner Brick House NW 333° 147.29'
SW Corner House Foundation NE 64° 76.28'

PA. 345 OTTAWA COUNTY
PEER APPROVED 12/12/94

Madon P. Nedwell


C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-11
Se O.C. Remon Iron & Cap in Cement and Set Monument Box Over It
O.C. Remon Tag & Nail in SE Side Oak AZ. 46° 39.29'
O.C. Remon Tag & Nail in SW Side Twin Oak AZ. 151° 59.23'
O.C. Remon Tag & Nail in SE Side Power Pole AZ. 217° 42.53'
O.C. Remon Tag & Nail in SE Side Twin Oak AZ. 321° 67.17'

Signed by John P. Clapp

Date Dec. 5, 1994

Surveyor's Michigan License No. 14091



FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983