

**SURVEY & REMONUMENTATION**

APR 05 1996

**COMMISSION**

**OTTAWA COUNTY REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in  
Ottawa Located In: Corner Code #  
(County)

1. Public Land Survey T5N R16W G-13 SW Cor Sec 34  
T R Park Twp.  
T R  
T R

2. Property Controlling S T R  
in Section S T R

3. Miscellaneous S T R  
Property in Sec. S T R

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

**RECORDED**  
95 NOV 15 PM 2:08  
*Phyllis Ballman*  
REGISTER OF DEEDS  
OTTAWA COUNTY, MI  
Register of Deeds Stamp & File Number

I, Steven Lampen, in a field survey on October 12, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

G-13  
GLO Survey Notes  
1832 - Surveyor, Lucius Lyon  
20" Sycamore is corner

G-13  
Unrecorded ties from 1981  
Found pinched pipe in monument box  
SW corner house foundation NE 86.56'  
16" Maple S 46.13'  
12" Spruce SE 54.63'  
Allegan corner W 124.66'

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

G-13  
Found pinched pipe in monument box and accepted it as a careful and faithful perpetuation of the position of the original corner  
SW corner house foundation AZ 47° 85.56'  
12" Maple AZ 179° 46.13'  
Allegan corner AZ 269° 124.66'

P.A. 345 OTTAWA COUNTY  
PEER APPROVED 10/23/95

*Steven Lampen*

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

G-13  
Set O.C. remon cap & iron in monument box  
SW corner house foundation AZ 46°54' 85.56'  
Set O.C. remon tag & nail NE side 16" Pine AZ 132°03' 55.25'  
Found nail & cap #14091 E side 12" Maple AZ 78°57' 46.13'  
Found nail & cap #14091 NE side 20" Beech AZ 327°32' 72.30'  
Allegan corner AZ 269°22'57" 124.66'  
This iron fits the monumented corners of Jenisons Park Subdivision



Signed by Steven Lampen

Date October 12, 1995

Surveyor's Michigan License No. 37279