

OTTAWA COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

93 NOV -8 PM 1:52

Phyllis Chalmers
REGISTER OF DEEDS
OTTAWA COUNTY, MI

For corners in
Ottawa

(County)

Located in:

Corner Code ##

1. Public Land Survey	T	5N	R	16W	H-3 (N 1/4 Sec 10)
	T		R		Park Twp.
	T		R		
	T		R		
2. Property Controlling in Section	S		T	R	
	S		T	R	
3. Miscellaneous Property in Sec.	S		T	R	
	S		T	R	

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, **David R. Greer**, in a field survey on **September 13**, 19 **93**, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	13	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

Recorded in Liber 1, Page 565
August 21, 1972
H-3

Recorded in Liber 5, Page 141
June 27, 1984
H-3

Found 2" Iron Pipe

Cast Iron Monument

30" Maple NW 29.50'
15" Maple NE 43.35'
12" Maple NE 60.87'
24" Maple SE 49.27'
18" Cherry S 26.10'

31" Maple SE 49.94'
16" Maple NE 43.83'
30" Maple NNW 30.93'
15" Maple NW 66.15'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

H-3

Found cast iron monument and accepted it as a careful and faithful perpetuation of the position of the original corner

31" Maple	SE	49.94'	30" Maple	NW	29.50'
16" Maple	NE	43.83'	15" Maple	NE	43.35'
30" Maple	NNW	30.93'	12" Maple	NE	60.87'
15" Maple	NW	66.15'	24" Maple	SE	49.27'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H-3

Found C.I.M. in monument box

AZ - Michigan State Grid Direction

O.C. Remon tag & nail in NW Side 12" Cherry	AZ.	51°48'	81.84'
O.C. Remon tag & nail in NE Side 10" Pine	AZ.	309°53'	80.59'
NW Cor Garage Wood	AZ.	200°38'	139.29'
O.C. Remon tag & nail in W Side 12" Oak	AZ.	180°49'	68.36'



Signed by

David R. Greer

Date

9/13/93

Surveyor's Michigan License No. 16042