

OTTAWA COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Phyllis Chalkman
REGISTER OF DEEDS
OTTAWA COUNTY, MI

For corners in
Ottawa

COMMISSION

(County)	Located In:	Corner Code #
1. Public Land Survey	T <u>5N</u> R <u>16W</u>	<u>H-9 (S 1/4 Sec 22)</u> <u>Park Twp.</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, David R. Greer, in a field survey on September 15, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

- A. Description of original monument and accessories and/or subsequent restoration:
- | | |
|------------------------------|------------------------------|
| Recorded in Liber 1 Page 365 | Recorded in Liber 2 Page 733 |
| May 11, 1972 | Jan 14, 1975 |
| H-9 | H-9 |
| Found Concrete Monument | Found Pinched Pipe Set CIM |
| Pinched Pipe N 27.42' | 12" Bl Cherry NE 20.97' |
| 14" Cherry N 47.15' | 12" Bl Cherry NW 20.85' |
| 16" Cherry NW 43.24' | 10" Bl Cherry N 67.53' |
| 30" Maple E 51.71' | 32" Maple SW 36.32' |
| | 8" White Pine SW 109.59' |

Recorded in Liber 3, Page 271
June 15, 1978
H-9
Found Concrete Monument
14" Cherry N 47.15'
18" Cherry NW 43.24'
30" Maple W 51.71'

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
- H-9
Found large angle iron and accepted it as a careful and faithful perpetuation of the position of the original corner
- | | | |
|------------------|----|---------|
| 12" Black Cherry | NW | 20.85' |
| 32" Maple | SW | 56.32' |
| 8" White Pine | SW | 109.59' |

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
- H-9
Set O.C. Remonumentation Iron & Cap
AZ - Michigan State Grid Direction
- | | | | |
|---|-------|---------|---------|
| O.C. Remon tag & nail in East Side 14" Cherry | AZ. | 0°15' | 95.51' |
| O.C. Remon tag & nail in SW Side 14" Maple | AZ. | 324°01' | 100.62' |
| O.C. Remon tag & nail in W Side 6" Maple | AZ. | 23°46' | 71.65' |
| O.C. Remon tag & nail in NE Side 12" Pine | AZ. | 154°25' | 44.30' |
| O.C. Remon tag & nail in SW Side 12" Pine | AZ. | 222°52' | 67.54' |
| CL Moument Box | AZ | 359°17' | 23.00' |
| CL-20" Wide Asphalt Road | North | | 20.5' |



Signed by David R. Greer Date 9/15/93
Surveyor's Michigan License No. 16042