

SURVEY & REMONUMENTATION

APR 24 1995

COMMISSION

OTTAWA COUNTY REMONUMENTATION LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

94 DEC 14 AM 9:42

Richard Robinson
REGISTER OF DEEDS
OTTAWA COUNTY, MI

For corners in

— Ottawa (County) Located In: Corner Code #

1. Public Land Survey	T <u>5N</u> R <u>16W</u>	<u>H-13 S1/4 Cor.</u>
	T _____ R _____	<u>Sec. 34</u>
	T _____ R _____	<u>Park Twp.</u>
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, John P. Clapp, in a field survey on November 18, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

H-13 Govt Land Office Survey Notes 1832 Surveyor, Lucius Lyon Set Post 28" Beech N89°E 58 links 26" Beech N67°W 14 links	H-13 Recorded in Liber 4, June 10, 1982 Set "T" Iron 24" Maple SE 41.41' 24" Maple SW 35.82' 24" Maple WSW 85.64'	Power Pole WSW 135.48' SE Cor Hse Fd NNW 91.42' SW Cor Hse Fd NW 123.75' Allegan Co. Cor S88° 98.20'
---	--	---

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

H-13
Found "T" iron in monument box and accepted it as a careful and faithful perpetuation of the position of the original corner

SW Corner House Foundation	AZ 315°	123.76'
20" Maple	AZ 139°	41.40'
Allegan County Corner	AZ 270°	98.18'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:


H-13
Set O.C. Remon Cap & Iron in Monument Box

SE Corner House Foundation	AZ. 23°21'	201.19'
SW Corner House, Brick	AZ.315°25'	123.76'
SE Corner House Foundation	AZ.226°26'	150.00'
Fd Nail & Cap #16042 NE Side 20" Maple	AZ.138°52'	41.40'
CL 12" Maple Remon Tag & Nail	AZ.329°17'	54.47'
Allegan Corner	AZ. 270°23'07"	98.18'

P.A. 345 OTTAWA COUNTY
PEER APPROVED 12/12/94
Madog D. Hedewell

Signed by John P. Clapp *John P. Clapp*
Surveyor's Michigan License No. 14091

Date Dec. 5, 1994



FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983