

1000

RECORDED

93 NOV -8 PM 1:53

OTTAWA COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

REGISTER OF DEEDS
OTTAWA COUNTY, MI

For corners in
Ottawa

(County)	Located In:	Corner Code #
1. Public Land Survey	T <u>5N</u> R <u>16W</u>	<u>1-4 (E 1/4 Sec 10)</u> <u>Park Twp.</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, David R. Greer, in a field survey on September 15, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Recorded in Liber 3 Page 29 January 29, 1978 I-4 Steel Bar	Recorded in Liber 1, Page 565 August 21, 1972 I-4 Found Iron Pipe	Recorded in Liber 5, Page 114 June 5, 1984 I-4 Found Cast Iron Monument
Tele Pole NE 48.29'	10" Sassafras SE 39.34'	11" Sassafras ESE 69.98'
24" Maple NW 61.18'	10" Ironwood SW 48.08'	LP SE 42.36'
Light Pole SE 42.18'	12" Maple NW 31.87'	19" Maple WSW 62.47'
	Tele. Pole NE 33.16'	24" Maple WNW 60.95'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-4
 Found cast iron monument and accepted it as a careful and faithful perpetuation of the position of the original corner
 11" Sassafras ESE 69.96'
 LP SE 42.36'
 19" Maple WSW 62.47'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-4
 Found C.I.M. in monument box
 AZ - Michigan State Grid Direction
 O.C. Remon tag & nail in SW Side 10" Maple AZ. 305°45' 110.88
 O.C. Remon tag & nail in NW Side 46" Oak AZ. 218°09' 90.69'
 O.C. Remon tag & nail in NE Side 10" Maple AZ. 138°21' 79.09'
 O.C. Remon tag & nail in SE Side 12" Oak AZ. 243°59' 93.43'



Signed by David R Greer
 Surveyor's Michigan License No. 16042

Date 9/15/93