

# SURVEY & REMONUMENTATION

APR 24 1995

COMMISSION

**OTTAWA COUNTY REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

RECORDED

94 DEC 14 AM 10:02

*Edythe Ballman*  
REGISTER OF DEEDS  
OTTAWA COUNTY, MI

For corners in

<u>Ottawa</u> <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T <u>5N</u> R <u>16W</u>	<u>I-6 (W1/4 Cor. Sec 14)</u>
	T _____ R _____	<u>Park Twp.</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

I, John P. Clapp, in a field survey on November 29, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

I-6 Govt Land Office Survey Notes 1832-Surveyor, Calvin Britain Set 1/2 Mile Post 16" Pine N59 1/2°W 15 links 16" Pine S59 1/2°E 8 links	I-6 Recorded in Liber 1 Page 229, Jan 11, 1972 Set Cast Iron Monument 12" Oak SW 52.80' 12" Pine W 45.18' Power Pole SE 58.67' 20" Oak SE 72.07' 16" Oak NE 51.57'	I-6 Recorded in Liber 6 Page 173, Oct 11, 1991 Reset CIM from previous ties 20" Oak NE 52.48' 13" Ash NW 40.69' 30" Oak SE 72.77' 17" Tw Oak SW 50.40'
---	--	---

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-6  
Found cast iron monument in monument box and accepted it as a careful and faithful perpetuation of the position of the original corner


Found Nail in SE Side 17" Twin Oak	AZ 219°	50.34'
Found Nail in NE Side 16" Ash	AZ 307°	40.70'
Found Nail in NW Side 28" Oak	AZ 42°	52.42'
Found Nail in E Side 12" White Pine	AZ 272°	45.02'

*Maday D. McDowell*  
P.A. 645 OTTAWA COUNTY  
PEER APPROVED 12/12/94

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-6  
Found Cast Iron Monument in Monument Box

O.C. Remon Tag & Nail SE Side 17" Twin Oak	AZ. 219°	50.42'
O.C. Remon Tag & Nail SW Side 19" Oak	AZ. 137°	51.83'
O.C. Remon Tag & Nail NW Side 28" Oak	AZ. 42°	52.69'
O.C. Remon Tag & Nail NE Side 16" Ash	AZ. 307°	40.68'



Signed by John P. Clapp Date Dec 2, 1994  
Surveyor's Michigan License No. 14091