

1993

OTTAWA COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED
93 NOV -8 PM 1:52

Phyllis Chalmers
REGISTER OF DEEDS
OTTAWA COUNTY, MI

For corners in
Ottawa
(County)

	Located In:	Corner Code #
1. Public Land Survey	T <u>5N</u> R <u>16W</u>	<u>1-8 (E 1/4 Sec 22)</u>
	T _____ R _____	<u>Park Twp.</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, David R. Greer, in a field survey on October 8, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	A
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Recorded in Liber 2 Page 791
July 29, 1975
I-8
Found 1/2" rod
24" Maple SE 43.51'
Power Pole NE 65.96'
Telephone Pole NW 45.61'
Telephone Pole SW 40.55'

Recorded in Liber 2 Page 733
January 14, 1975
I-8
Found Iron Bar
14" Maple SE 43.45'
Telephone Pole SW 40.55'
Tele. Support Pole NW 45.60'
Power Pole NE 55.95'

Recorded in Liber 2
Page 513 July 9, 1974
I-8
Found Chisel
Power Pole SE 46.78'
18" Oak SE 43.56'
Tele. Pole SW 40.52'
Power Pole NE 55.94'
Power and
Tele. Pole NW 89.62'
CL N 8.18'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-8
Found steel bar and accepted it as a careful and faithful perpetuation of the position of the original corner
Power Pole SE 46.78'
18" Oak SE 43.56'
Telephone Pole SW 40.52'
Power Pole NE 55.94'
Power & Tele.
Pole NW 89.62'
CL N 8.18'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-8
Found C.I.M. in monument box. Set O.C. Remonumentation Iron & Cap in Monument Box.
AZ - Michigan State Grid Direction
NW Cor House Foundation AZ. 116°54' 111.53'
SW Cor Brick Wall AZ. 43°12' 160.01'
Found P.K. & Cap in SE Side Power Pole AZ. 55°31' 57.25'
SE Cor House Foundation AZ. 314°41' 121.62'
NW Cor House, Wood AZ. 232°02' 129.86'



Signed by David R. Greer
Surveyor's Michigan License No. 16042

Date 10/8/93