

SURVEY & REMONUMENTATION

APR 24 1995

COMMISSION

**OTTAWA COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE**
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

94 DEC 14 AM 9:42

Debbie Carloman
REGISTER OF DEEDS
OTTAWA COUNTY, MI

For corners in

<u>Ottawa</u> <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T <u>5N</u> R <u>R16W</u>	<u>I-10 W1/4 Cor.</u>
	T _____ R _____	<u>Sec 26</u>
	T _____ R _____	<u>Park Twp.</u>
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, John P. Clapp, in a field survey on November 22, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

I-10 Govt Land Office Survey Notes 1832 Surveyor, Calvin Britain Set Post 30" Elm S63°W 26 links 12" Beech N37°E 7 links	I-10 Recorded in Liber 4 Page 175, May 19, 1981 Fd P.K. Nail in place of removed conc. monument Set 3/4" Iron Pipe Power Pole NW 50.17' CL Hydrant NNE 42.22' Power Pole NE 80.30' Power Pole SW 73.73'	I-10 Recorded in Liber 5 Page 304 Fd 3/4" Iron Pipe 14" Pine NW 56.30' 20" Maple NE 68.00' 24" Maple ENE 54.02' 18" Maple SE 58.40' 14" Pine SW 74.56'
---------------------------------------------------------------------------------------------------------------------------------------------	-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------	------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-10
 Found 3/4" pipe and accepted it as a careful and faithful perpetuation of the position of the original corner

Found P.K. S Side Power Pole	AZ 297°	50.19'
Found Nail & Tag NE Side 23" Pine	AZ 311°	56.37'
CL Hydrant	AZ 34°	42.22'
Found P.K. S Side Power Pole	AZ 82°	80.30'
Found Scar S Side 32" Maple	AZ 71°	54.00'
Found Nail & Tag NW Side 19" Pine	AZ 245°	74.50'

P.A. 345 OTTAWA COUNTY
PEER APPROVED 12/12/94

Wesley P. Medwell


C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-10
 Set O.C. Remon Iron & Cap & Set Monument Box Over It

O.C. Remon Tag & Nail S Side 32" Maple	AZ. 71°	53.95'
O.C. Remon Tag & Nail W Side 26" Maple	AZ. 154°	58.49'
O.C. Remon Tag & Nail SE Side 19" Pine	AZ. 245°	74.31'
O.C. Remon Tag & Nail S Side 23" Pine	AZ. 311°	56.30'

Signed by John P. Clapp *John P. Clapp* Date Dec 5, 1994

Surveyor's Michigan License No. 14091



FORM APPROVED BY MICHIGAN STATE SURVEYORS, JAN. 28, 1971
 REVISED MAY 14, 1975
 REVISED JAN., 1983