

**OTTAWA COUNTY REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE**

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in  
Ottawa \_\_\_\_\_  
(County)

Located In:

Corner Code #

- |                                    |              |                 |
|------------------------------------|--------------|-----------------|
| 1. Public Land Survey              | T5N R16W     | I-11            |
|                                    | T R          | SE cor. Sec. 27 |
|                                    | T R          | Park Twp.       |
|                                    | T R          |                 |
| 2. Property Controlling in Section | S27 T5N R16W |                 |
|                                    | S T R        |                 |
| 3. Miscellaneous Property in Sec.  | S T R        |                 |
|                                    | S T R        |                 |

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Steven Lampen \_\_\_\_\_, in a field survey on December 5, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

I-11	GLO
GLO - Brookfield - 1832	North between Sections 26 and 27
North between Sections 34 and 35	33.28' left lake and set post
38.43' Black River Lake and set meander post	40.00' set 1/2 mile post
40.00' 1/2 mile post in Lake	
80.00' set corner in lake to Sections 26, 27, 34 and 35	

Section line between Sections 26 and 27 is shown on the Plat of First Addition to Waukazoo - 1905 and Elm Grove Park Subdivision.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

I-11  
Found no field evidence or survey record that I-11 had ever been located since the original GLO Survey. Calculated position of I-11 by using double proportionate measurement using corners I-10, I-12, G-11 and M-11. Re-established section line between Sections 26 and 27 by using the plats listed in Part A for East and West location and proportioned the GLO measurement for North and South location. See sketch on back. Set Ottawa County Remonumentation iron and cap as a reference monument on the section line between Sections 26 and 27.

Calculated position of I-11 and the section line between Sections 26 and 27 are accepted as a careful and faithful re-establishment of the position of the original corner and section line.

PA. 345 OTTAWA COUNTY  
PEER APPROVED 12-9-96

*S. P. J.*

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

I-11 See sketch on back Azimuths = Michigan State Plan grid direction  
Reference monument - Ottawa County Remonumentation iron and cap on section line between Sections 26 and 27

SW corner steel seawall, cap	168° 41'	49.85'
SE corner steel seawall, cap	263° 45'	33.41'
NE corner garage foundation	341° 16'	143.91'
SW corner bay window, brick	112° 59'	140.91'
South end asphalt road pavement	0° 14'	8'
North Shore Lake Macatawa	180° 14'	39'
I-10 = Remon. iron in monument box	0° 13' 45"	339.94'
GLO meander post	180° 13' 45"	78.71'



Signed by Steven Lampen Date DECEMBER 13, 1996

Surveyor's Michigan License No. 37279

