

SURVEY & REMONUMENTATION

APR 24 1995

COMMISSION

OTTAWA COUNTY REMONUMENTATION LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

95 DEC 14 AM 9:41

Deborah A. Robinson
REGISTER OF DEEDS
OTTAWA COUNTY, MI

For corners in

Ottawa <small>(County)</small>	Located In:	Corner Code #	
1. Public Land Survey	T <u>5N</u> R <u>16W</u>	<u>J-3 (N1/4 Cor Sec 11)</u>	
	T _____ R _____	<u>Park Twp.</u>	
	T _____ R _____		
	T _____ R _____		
2. Property Controlling in Section	S _____ T _____ R _____		
	S _____ T _____ R _____		
3. Miscellaneous Property in Sec.	S _____ T _____ R _____		
	S _____ T _____ R _____		
4. Lot No. _____, Recorded Plat _____			
5. Private Claims _____			

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, John P. Clapp, in a field survey on November 29, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

J-3 Govt Land Office Survey Notes
1832-Surveyor, Calvin Britain
Set Post
10" Pine S10°E 26 links
7" Maple N55°E 26 links

J-3 Recorded in Liber 1
Page 339, April 10, 1972
Found Iron Pipe from Old County Ties
Set Cast Iron Monument
Telephone Pole N 24.70'
Triple Birch ENE 57.60'
12" Pine SW 63.05'
SW Cor House NE 85.36'
SE Cor House NE 110.03'

3. Description of corner evidence found and/or method applied in restoring or reestablishing corner:


J-3
Found cast iron monument in monument box and accepted it as a careful and faithful perpetuation of the position of the original corner
SE Corner Brick House AZ 43° 110.03'

P.A. 345 OTTAWA COUNTY

Deborah P. Redwood
PEER APPROVED 12/12/94

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J-3
Found Cast Iron Monument in Monument Box (top missing)
SE Corner Brick House AZ. 43° 110.03'
O.C. Remon Tag & Nail E Side 32" Maple AZ. 207° 80.64'
O.C. Remon Tag & Nail NW Side 22" Pine AZ. 241° 63.51'
O.C. Remon Tag & Nail NE Side Power Pole AZ. 290° 256.78'



Signed by John P. Clapp *John P. Clapp* Date Dec 2, 1994

Surveyor's Michigan License No. 14091