

SURVEY & REMONUMENTATION

APR 24 1995

COMMISSION

OTTAWA COUNTY REMONUMENTATION LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

94 DEC 14 AM 9:42

Richard A. Robinson
REGISTER OF DEEDS
OTTAWA COUNTY, MI

For corners in

<u>Ottawa</u> <small>(County)</small>	Located In:	Corner Code #	
1. Public Land Survey	T <u>5N</u> R <u>16W</u>	<u>J-5 N1/4 Cor</u>	
	T _____ R _____	<u>Sec 14</u>	
	T _____ R _____	<u>Park Twp.</u>	
	T _____ R _____		
2. Property Controlling in Section	S _____ T _____ R _____		
	S _____ T _____ R _____		
3. Miscellaneous Property in Sec.	S _____ T _____ R _____		
	S _____ T _____ R _____		

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5										⊙			
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, John P. Clapp, in a field survey on November 28, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

<p>J-5 Govt Land Office Survey Notes 1832-Surveyor, Calvin Britain Set Post 7" Black Ash N13°W 7 links 8" Black Ash S1°W 26 links</p>	<p>J-5 Recorded in Liber 2 Page 87, March 23, 1973 Found Railroad Spike, Set Cast Iron Monument 8" Red Pine NE 47.15' T. Pole NW 43.74' 12" Maple SW 49.44' 16" Black Gum SE 43.03'</p>
--	--

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

J-5
Found cast iron monument in monument box and accepted it as a careful and faithful perpetuation of the position of the original corner.
Found Nail in Southwest Side 14" Pine AZ 32° 47.01'

P.A. 345 OTTAWA COUNTY
PEER APPROVED 12/12/94

Richard P. Redwood

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:


<p>J-5 Found Cast Iron Monument in Monument Box O.C. Remon Tag & Nail in NW Side 14" Pine NE Cor Concrete Porch House # 13644 O.C. Remon Tag & Nail in N Side 42" Maple O.C. Remon Tag & Nail in SSW Side 14" Pine</p>	<p>AZ. 44° 54.85' AZ. 145° 138.29' AZ. 253° 105.39' AZ. 298° 87.19'</p>
---	---

Signed by John P. Clapp

John P. Clapp

Date Dec 5, 1994

Surveyor's Michigan License No. 14091



FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983