

OTTAWA COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE

COMMISSION Filing Requirement of Act 74, Mich. P.A. 1970

REGISTER OF DEEDS OTTAWA COUNTY, MI

For corners in Ottawa

Table with columns: Located In: (County), Corner Code #, and survey details for Public Land Survey, Property Controlling, and Miscellaneous Property in Sec.

Register of Deeds Stamp & File Number

4. Lot No. , Recorded Plat
5. Private Claims

Grid table with columns A-M and rows 1-13, containing numbers 1-36 and a dot at row 7, column J.

I, David R. Greer, in a field survey on September 15, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Recorded in Liber 1 Page 599, August 20 1972

J-7

- Nail on side of Power Pole SSE 21.38'
Cut Cross ("X") in S end Culvert SW 16.23'
Cut Cross ("X") in N end Culvert NW 29.71'
CL Pavement N 6.3'
Fence line to the North W 17.3'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

J-7

Found cast iron monument and accepted it as a careful and faithful perpetuation of the position of the original corner

- Cut cross ("X") in S end culvert SW 16.23'
Cut cross ("X") in N end culvert NW 29.71'
CL Pavement N 6.3'
Fence line to the North W 17.3'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J-7

Found C.I.M. in monument box

AZ - Michigan State Grid Direction

- CL 20' asphalt road pavement AZ. North 6.6'
CL N & S culvert & N & S ditch AZ. West 10'
O.C. Remon tag & nail in W Side 6" Maple Cluster AZ. 179°54' 75.60'
O.C. Remon tag & nail in NW Side 16" Poplar AZ. 46°17' 49.03'
O.C. Remon tag & nail in E Side 18" Ash AZ. 351°33' 33.62'
Cut "X" S end concrete culvert AZ. 222°05' 16.27'

Signed by David R Greer
Surveyor's Michigan License No. 16042

Date 9/15/93

