

RECORDED

93 NOV -8 PM 1:53

OTTAWA COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

REGISTER OF DEEDS OTTAWA COUNTY, MI

For corners in Ottawa

Table with columns: (County), Located In: (5N, 16W), Corner Code ## (J-9 (S 1/4 - 23), Park Twp.)

Register of Deeds Stamp & File Number

4. Lot No. , Recorded Plat
5. Private Claims

Grid table with columns A-M and rows 2-13, containing numbers 1-36 and a dot at row 9, column J.

David R. Greer, in a field survey on September 15, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- Recorded in Liber 2 Page 273 August 7, 1973
J-9
Found Concrete Monument Midway on True Line
"X" on Culvert NE 20.65'
Fence Post NW 41.90'
6" Tree NW 39.66'
"X" on Culvert NW 22.15'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- J-9
Found C.I.M. and accepted it as a careful and faithful perpetuation of the position of the original corner
"X" on Culvert NE 20.65'
Fence Post NW 41.90'
"X" on Culvert NW 22.15'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- J-9
Found C.I.M. in monument box. Set Ottawa County Remonumentation Iron & Cap
AZ - Michigan State Grid Direction
O.C. Remon tag & nail in W Side 6" Cherry AZ. 327°00' 38.47'
O.C. Remon tag & nail in W Side 4" maple AZ. 8°00' 70.22'
O.C. Remon tag & nail in S Side Twin 8" Ash AZ. 115°07' 22.91'
O.C. Remon tag & nail in NW Side 8" Ash AZ. 226°23' 18.41'



Signed by David R. Greer

Date 9/15/93

Surveyor's Michigan License No. 16042