

**OTTAWA COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE**

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Ottawa _____
(County)

Located In:

Corner Code #

- | | | | |
|------------------------------------|-----|------|------------------|
| 1. Public Land Survey | T5N | R16W | J-11 |
| | T | R | South 1/4 corner |
| | T | R | Section 26 |
| | T | R | Park Twp. |
| 2. Property Controlling in Section | S26 | T5N | R16W |
| | S | T | R |
| 3. Miscellaneous Property in Sec. | S | T | R |
| | S | T | R |

RECORDED

96 DEC 20 PM 12:20

Phyllis Redman
REGISTER OF DEEDS
OTTAWA COUNTY, MI

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Steve Lampen _____, in a field survey on December 5 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

J-11 Glo-Brookfield-1832 1/4 Section post on true line W. oak 10 N 40 W 42' do 14 S 42 E 26'	J-11 is not recorded J-11 appears on the plat of Waukazoo - 1901 and Plat of First Addition to Waukazoo - 1905 but is not related to the lot lines with any dimensions J-11 is referenced by Hiawatha Resubdivision...1963 but this reference was discredited and not used.
--	---

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

J-11 Found no field evidence or survey record that J-11 had ever been located since the original GLO survey. Reestablished J-11 mid-way and on line between I-11 and K-11. Corner is now under a house. Set witness monument on N and S 1/4 line 230.0 feet North of J-11. See sketch on back.


**PA. 345 OTTAWA COUNTY
PEER APPROVED 12-9-96**

M.P.N.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J-11
Reference Monument - Set Ottawa County Remonumentation iron and cap on N and S 1/4 line 230 feet North of J-11 Az. = Michigan State Plane Grid Direction.

J-11	180° 43' 18"	230.0'
J-10	0° 43' 18"	2406.75'
Remon tag South side 20" Beech	289° 19'	74.75'
Remon tag W'ly side 34" Oak	229° 00'	51.16'
Hydrant, Top centerline	84° 53'	184.08'
Remon tag East side 24" Beech	35° 57'	88.62'



Signed by Steven Lampen

Date DECEMBER 13, 1996

Surveyor's Michigan License No. 37279

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983
ADAPTED FOR WORD PROCESSING MARCH, 1993

