

SURVEY & REMONUMENTATION

APR 24 1995

COMMISSION

**OTTAWA COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE**
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

94 DEC 14 AM 9:42

For corners in

Ottawa (County) Located In: Corner Code #
 1. Public Land Survey T 5N R 16W J13 S1/4 Cor.
 T R Sec. 35
 T R Park Twp.
 T R
 2. Property Controlling S T R
 in Section S T R
 3. Miscellaneous S T R
 Property in Sec. S T R

Richard C. Williams
REGISTER OF DEEDS
OTTAWA COUNTY, MI

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, John P. Clapp, in a field survey on November 18, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

J-13 Govt Land Office Survey Notes 1832-Surveyor, Lucius Lyon Set Post 20" Beech N77°E 36 links 11" Beech N73°W 18 links	J-13 Recorded in Liber 2, Page 21 Feb 16, 1973 Fd 3/4" iron pipe Trans Pole NNW 69.86' Guy Pole SE 28.42' 20" Oak WNW 53.18' CL St Sign NE 44.42'	J-13 Recorded in Liber 5 Page 310 Mar 18, 1988 Found Iron in Mon. Box 8" Pine ENE 69.90' SE Cor Hse NW 102.44' 16" Tree SSE 41.39' 10" Maple SW 53.64' Power Pole NNW 69.96' Iron W 88.33'
--	---	--

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

J-13
Found steel bar in monument box and accepted it as a careful and faithful perpetuation of the position of the original corner
 Allegan Corner W 88.36'
 SE Cor Brick House N38°W 102.48'
 8" Pine ENE 69.90'

P.A. 345 OTTAWA COUNTY
 PEER APPROVED 12/12/94


Richard C. Williams

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J-13
 Set O.C. Remon Iron and Cap in Monument Box
 SE Corner House, Brick AZ.322°19' 102.48'
 Found nail & tag #14091 SE Side 10" Pine AZ. 60°49' 69.90'
 O.C. Remon tag & nail NW Side 18" Oak AZ.231°51' 47.92'
 NW Cor House Foundation AZ.128°53' 157.06'
 Allegan Corner AZ.270°10'30" 88.36'

Signed by John P. Clapp
 Surveyor's Michigan License No. 14091

Date Dec 5, 1994



FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
 REVISED MAY 14, 1975
 REVISED JAN., 1983