

SURVEY & REMONUMENTATION

APR 24 1995

COMMISSION

**OTTAWA COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

RECORDED

94 DEC 14 AM 9:41

Richard L. Redmond
REGISTER OF DEEDS
OTTAWA COUNTY, MI

For corners in

<u>Ottawa</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>5N</u> R <u>16W</u>	<u>K-3 NW Cor Sec 12</u>
	T _____ R _____	<u>Park Twp.</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, John P. Clapp, in a field survey on November 29, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3										⊕		
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

K-3	K-3
Govt Land Office Survey Notes	Recorded in Liber 1
1832-Surveyor, Calvin Britain	Page 75, Sep 22, 1971
Set Corner Post	Fd Bolt & Pinched Pipe
12" Wh. Ash N48°W 10 links	Set Cast Iron Monument
9" Hemlock S48°E 7 links	6" Maple SW 131.40'
	St. Sign SE 33.39'
	Guard Post NE 23.66'
	Guard Post NW 25.64'

K-3
Recorded in Liber 1,
Page 271, Feb 15, 1972
Fd Cast Iron Monument
Street Sign SE 33.30'
T. Pedestal SE 41.75'
Culvert Post. NE 23.65'
Culvert Post NW 26.66'
6" Beech SW 131.52'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:


K-3
Found cast iron monument in monument box (top missing) and accepted it as a careful and faithful perpetuation of the original corner
CL Street Sign AZ 141° 41.58' ±
CL Telephone Pedestal for Underground AZ 134° 41.96' ±

P.A. 345 OTTAWA COUNTY

Madison P. Redmond PEER APPROVED 12/12/94

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-3
Found Cast Iron Monument (top missing) in Monument Box
O.C. Remon Tag & Nail SE Side Power Pole AZ. 44° 498.92'
O.C. Remon Tag & Nail N Side Power Pole AZ. 98° 356.14'
N.W. Corner Brick Ameritech Building AZ. 254° 280.96'
O.C. Remon Tag & Nail SW Side Power Pole AZ. 307° 38.94'



Signed by John P. Clapp
Surveyor's Michigan License No. 14091

Date Dec 2, 1994