

SURVEY & REMONUMENTATION

APR 24 1995

COMMISSION

OTTAWA COUNTY REMONUMENTATION LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

94 DEC 14 AM 10:03

Phyllis Robinson
REGISTER OF DEEDS
OTTAWA COUNTY, MI

For corners in

<u>Ottawa</u> <small>(County)</small>	Located In:	Corner Code #:	
1. Public Land Survey	T <u>5N</u> R <u>16W</u>	<u>K-4 (W1/4 Cor Sec 12)</u>	
	T _____ R _____	<u>Park Twp.</u>	
	T _____ R _____	_____	
	T _____ R _____	_____	
2. Property Controlling in Section	S _____ T _____ R _____	_____	
	S _____ T _____ R _____	_____	
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____	
	S _____ T _____ R _____	_____	
4. Lot No. _____, Recorded Plat _____			
5. Private Claims _____			

Register of Deeds Stamp & File Number

I, John P. Clapp, in a field survey on November 28, 1994

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

<p>K-4 Govt Land Office Survey Notes 1832-Surveyor, Calvin Britain Set 1/2 Mile Post 18" Hemlock N12°E 17 links 10" Beech S18°W 25 links See reverse side for additional recordings (Liber 5, Page 275)</p>	<p>K-4 Recorded in Liber 1 Page 271, Feb 15, 1972 Fd Iron Pipe 6" Oak P. Pole P. Pole 14" Oak CL St Sign</p>	<p>K-4 Recorded in Liber 5 Page 142 Jun 27, 1984 Fd Iron Pipe Set Cast Iron Monument Power Pole SE 50.33' Power Pole SW 69.34' 20" Oak WNW 91.47' 7" Poplar NW 76.47'</p>
--	---	--

3. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-4
Found cast iron monument in monument box and accepted it as a careful and faithful perpetuation of the position of the original corner

Found Nail in NW Side Power Pole	AZ 146°	49.86'
Found Nail in SW Side Power Pole	AZ 146°	50.31'
Found Nail & Tag in NE Side P. Pole	AZ 248°	68.95'
Found Nail in N Side Power Pole	AZ 248°	69.33'

Maday P. Nedwell
P.A. 345 OTTAWA COUNTY
PEER APPROVED 12/12/94


C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-4
Found Cast Iron Monument in Monument Box

O.C. Remon Tag & Nail E Side Power Pole	AZ.	7°	285.01'
O.C. Remon Tag & Nail NE Side Power Pole	AZ.	146°	50.45'
O.C. Remon Tag & Nail SE Side Power Pole	AZ.	248°	69.45'
O.C. Remon Tag & Nail SW Side 14" Oak	AZ.	292°	119.05'

Signed by John P. Clapp Date Dec 5, 1994

Surveyor's Michigan License No. 14091



FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN 28, 1971
REVISED JULY 14, 1976
REVISED JAN., 1983

K-4

Recorded in Liber 5, Page 275

August 17, 1987

Cast Iron Monument

Power Pole	SE	50.33'
Power Pole	SW	69.34'
20" Oak	WNW	91.47'
7" Poplar	NW	76.47'