

# SURVEY & REMONUMENTATION

APR 24 1995

COMMISSION

## OTTAWA COUNTY REMONUMENTATION LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

96 DEC 14 AM 9:41

*Phyllis Robinson*  
REGISTER OF DEEDS  
OTTAWA COUNTY, MI

For corners in

Ottawa <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T <u>5N</u> R <u>16W</u>	<u>K-6 W1/4 Cor.</u>
	T _____ R _____	<u>Sec 13</u>
	T _____ R _____	<u>Park Twp.</u>
	T _____ R _____	
2. Property Controlling in Section	S _____ T _____ R _____	
	S _____ T _____ R _____	
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	
	S _____ T _____ R _____	

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, John P. Clapp, in a field survey on November 18, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

<p>K-6 Govt Land Office Survey Notes 1832-Surveyor, Calvin Britain 8" Black Ash is Post</p>	<p>K-6 Recorded in Liber 1 Page 367, May 11, 1972 Found Angle Iron Tri. 8" Maple NW 59.80' Tri. 8" Maple W 60.82' 6" Sassafras E 78.23'</p>	<p>K-6 Recorded in Liber 5 Page 274, Aug. 17, 1987 Cast Iron Monument 10" Black Cherry W 41.72' 15" Pine SE 84.33' Tri 14" Poplar SSW 70.15' 17" Maple NW 58.98'</p>
---	---	--

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-6		
Found cast iron monument in monument box and accepted it as a careful and faithful perpetuation of the position of the original corner		
Found Nail in N Side 12" Black Cherry	AZ. 277°	41.72'
Found Nail in SW Side 15" Pine	AZ. 152°	84.29'
Found Flagging in Scar SE Side 19" Maple	AZ. 317°	58.93'

P.A. 345 OTTAWA COUNTY


*Wesley D. Nedwell* PEER APPROVED 12/12/94

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-6		
Cast Iron Monument in Monument Box		
O.C. Remon Tag & Nail NW Side 10" Wh. Pine	AZ. 49°	45.97'
O.C. Remon Tag & Nail NE Side 15" Pine	AZ. 152°	84.00'
O.C. Remon Tag & Nail E Side 18" Tri. Poplar	AZ. 193°	94.80'
O.C. Remon Tag & Nail SW Side 19" Maple	AZ. 317°	59.24'

Signed by John P. Clapp  
Surveyor's Michigan License No. 14091

Date Dec. 5, 1994



FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971  
REVISED MAR. 14, 1975  
REVISED JAN., 1983