

OTTAWA COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

*David R. Greer*  
REGISTER OF DEEDS  
OTTAWA COUNTY, MI

For corners in  
**Ottawa**

COMMISSION

(County)	Located In:	Corner Code #
1. Public Land Survey	T <u>5N</u> R <u>16W</u>	<u>K-7 (NE Sec 23)</u>
	T _____ R _____	<u>Park Twp.</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, **David R. Greer**, in a field survey on **September 15**, 19 **93**

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below.

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

Recorded in Liber 1, Page 367  
 May 11, 1972 K-7  
 Found Iron  
 Power Pole NW 38.87'  
 Support Pole SE 48.85'  
 Stop Sign SW 49.24'  
 Street Sign SE 44.60'  
 8" Pine NE 64.47'

Recorded in Liber 5, Page 274  
 August 17, 1984 K-7  
 Cast Iron Monument  
 Guy Pole SE 47.72'  
 Power Pole NW 38.88'  
 8" Pine NE 56.66'  
 7" Blk. Cherry NW 76.62'

Recorded in Liber 6, Page 265  
 March 29, 1993 K-7  
 Found PK with Nail and Tag  
 PP N&T SW Side N50°W 38.87'  
 8" Pine N&T NW Side N35°E 56.72'  
 14" Pine Nail NE Side S45°E 66.37'  
 Guy Pole Nail SE Side S44°E 48.78'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-7  
 Found P.K. Nail and accepted it as a careful and faithful perpetuation of the position of the original corner  
 Power Pole N&T SW Side N50°W 38.87'  
 8" Pine N&T SW Side N35°E 56.72'  
 14" Pine Nail NE Side S45°E 66.37'  
 Guy Pole Nail SE Side S44°E 48.78'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-7  
 Found P.K. per HEI records. Set Ottawa County Remonumentation Iron & Cap.  
 AZ - Michigan State Grid Direction  
 O.C. Remon tag & nail in SW Side 10" Pine AZ. 325°13' 95.93'  
 O.C. Remon tag & nail in W Side 10" Pine AZ. 28°09' 63.04'  
 O.C. Remon tag & nail in SW Side 10" Pine AZ. 129°04' 66.45'  
 NE Cor. Brick Sign AZ. 224°25' 115.94'

Signed by *David R. Greer*  
 Surveyor's Michigan License No. 16042

Date 9/15/93

