

1833

OTTAWA COUNTY REMONUMENTATION

RECORDED

93 NOV -8 PM 1:57

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

REGISTER OF DEEDS
OTTAWA COUNTY, MI

For corners in
Ottawa

COMMISSION

(County)	Located In:	Corner Code #
1. Public Land Survey	T 5N R 16W	K-8 (E 1/4 - 23)
	T _____ R _____	Park Twp.
	T _____ R _____	
	T _____ R _____	
2. Property Controlling in Section	S _____ T _____ R _____	
	S _____ T _____ R _____	
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	
	S _____ T _____ R _____	
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

I, David R. Greer, in a field survey on September 15, 19 93

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

Recorded in Liber 1 Page 387 May 11, 1972 K-8 Set Iron Pipe from Old Witness	Recorded in Liber 4, Page 326 June 10, 1982 K-8 1/2" Iron	Recorded in Liber 6 Page 255 March 29, 1993 K-8 Broken P.K. Nail
NW House Cor SE 126.39'	NW House Cor SE 126.39'	SE Cor House #230 N45°W 103.23'
Power Pole NE 65.38'	Power Pole NE 65.99'	N&T NW Side PP N50°E 65.98'
36" Maple SW 99.56'	36" Maple SW 101.36'	NW Rim Empty Mon Box SE 0.8'
Tele Pole SW 52.89'	Tele Pole SW 52.97'	NW Cor House Foundation S25°E 126.39'
		N&T in SE Side Power Pole S30°W 53.41'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-8
Found P.K. Nail and accepted it as a careful and faithful perpetuation of the position of the original corner.

SE Cor Brick House No. 230	N45°W	103.23'
Nail & Tag in NW Side Power Pole	N50°E	65.98'
NW Rim Empty Mon. Box	SE	0.8'
NW Cor House Foundation	S25°E	126.39'
Nail & Tag SE Side Power Pole	S30°W	53.41'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-8
Set Ottawa County Remonumentation Iron & Cap.
AZ - Michigan State Grid Direction

NW Cor Garage Foundation	AZ. 139°50'	124.47'
NE Cor Garage Foundation	AZ. 223°21'	110.26'
SE Cor Garage Brick	AZ. 313°33'	103.26'
SW Cor House Brick	AZ. 30°58'	133.63'
CL Monument Box	AZ. SE	1.13'

Signed by David R. Greer
Surveyor's Michigan License No. 16042

Date 9/15/93

